



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
T (786) 315-2590 F (786) 315-2599
www.miamidade.gov/economy

PGT Industries, Inc.
1070 Technology Drive
North Venice, FL 34275

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.-

DESCRIPTION: Series "PGT" Clipped Extruded Aluminum Tube Mullion - L.M.I.

APPROVAL DOCUMENT: Drawing No. 6300JR, titled "Impact-Resistant Aluminum Tube Mullions", sheets 1 through 25 of 25, prepared by manufacturer, dated 08/29/11, with revision B dated 10/10/14, signed and sealed by Anthony Lynn Miller, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, model/series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises and renews NOA# 14-1105.01 and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by Manuel Perez, P.E.



MP
4/11/16

NOA No. 16-0218.03
Expiration Date: May 26, 2021
Approval Date: April 14 2016
Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

A. DRAWINGS

1. Manufacturer's die drawings and sections.
(Submitted under NOA No. 10-0819.05)
2. Drawing No. **6300JR**, titled "Impact-Resistant Aluminum Tube Mullions", sheets 1 through 25 of 25, dated 08/29/11, with revision B dated 10/10/14, prepared by manufacturer, signed and sealed by Anthony Lynn Miller, P.E.

B. TESTS

1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
6) Forced Entry Test, per FBC 2411.3.2.1, and TAS 202-94
along with marked-up drawings and installation diagram of clipped aluminum mullions, prepared by Fenestration Testing Lab, Inc., Test Report No. **FTL-6443** (samples A-1 thru E-1), dated 02/28/11, and addendum letter dated 05/05/11, signed and sealed by Marlin D. Brinson, P.E.
(Submitted under NOA No. 10-0819.05)

C. CALCULATIONS


1. Anchor verification calculations and structural analysis, complying with **FBC-2010** and with **FBC 5th Edition (2014)**, prepared by manufacturer, dated 01/29/15, signed and sealed by Anthony Lynn Miller, P.E.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

E. MATERIAL CERTIFICATIONS

1. None.


Manuel Perez, P.E.
Product Control Examiner
NOA No. 16-0218.03
Expiration Date: May 26, 2021
Approval Date: April 14 2016

PGT Industries, Inc.


NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

F. STATEMENTS

1. Statement letter of conformance, complying with **FBC-5th Edition (2014)**, dated February 15, 2016, issued by manufacturer, signed and sealed by Anthony Lynn Miller, P.E.
2. Statement letter of no financial interest, dated February 15, 2016, issued by manufacturer, signed and sealed by Anthony Lynn Miller, P.E.

G. OTHERS

1. Notice of Acceptance No. **14-1105.01**, issued to PGT Industries, Inc. for their Series **"PGT" Clipped Extruded Aluminum Tube Mullion – L.M.I.**, approved on 02/12/15 and expiring on 05/26/16.



Manuel Perez, P.E.


Product Control Examiner

NOA No. 16-0218.03


Expiration Date: May 26, 2021

Approval Date: April 14 2016

SUITABLE FOR ALL LOCATIONS REQUIRING
NON-IMPACT OR LARGE AND SMALL
MISSILE IMPACT-RESISTANT PRODUCTS



ADDITIONAL EXAMPLES OF MULL CONFIGURATIONS:



SEE CORRESPONDING DETAILS
FROM FIGURE 1 ABOVE.

STANDARDS USED:

- 2014 FLORIDA BUILDING CODE (FBC), 5TH EDITION
- ANSI/AF&PA NDS-2012 FOR WOOD CONSTRUCTION
- ALUMINUM DESIGN MANUAL, ADM-2010
- AISI-S100-07/S2-2010

GENERAL NOTES:

- 1) DETAILS SHOWN ARE FOR THE MULLION ONLY. ANCHORS SHOWN ARE IN ADDITION TO ANY ANCHORS REQUIRED FOR THE FENESTRATION PRODUCT INSTALLATION. TYPICAL APPLICATIONS ARE SHOWN. EACH SITUATION IS UNIQUE AND SHOULD BE EVALUATED BY AN EXPERIENCED INSTALLER FOR THE BEST INSTALLATION METHOD. OPTIONAL 1X OR 2X WOOD BUCKS IF USED, MUST BE ANCHORED PROPERLY TO TRANSFER LOADS AND ARE TO BE DESIGNED BY OTHERS.
- 2) THE TYPE AND NUMBER OF ANCHORS IS CRITICAL TO THE STRUCTURAL PERFORMANCE OF THE MULLED UNITS. MULLIONS HAVE BEEN TESTED AS "FREE-FLOATING" AND DO NOT NEED TO BE DIRECTLY ATTACHED TO THE MULLION CLIPS, BUT SHALL NOT HAVE A GAP OF MORE THAN 1/4" FROM THE CLIP.
- 3) THE ANCHORAGE METHODS SHOWN HAVE BEEN DESIGNED TO RESIST THE WINDLOADS CORRESPONDING TO THE REQUIRED DESIGN PRESSURE. MULLIONS ARE CALCULATED TO DEFLECT NO MORE THAN L/180. THE 1/3 STRESS INCREASE WAS NOT USED IN THIS ANCHOR EVALUATION. THE 1.6 LOAD DURATION FACTOR WAS USED FOR THE EVALUATION OF WOOD SCREWS.
- 4) PROPER SEALING OF ENTIRE ASSEMBLY IS THE RESPONSIBILITY OF OTHERS AND IS BEYOND THE SCOPE OF THESE INSTRUCTIONS.
- 5) USE THE COMBINED WIDTH OR HEIGHT OF ONLY TWO ADJACENT FENESTRATION PRODUCTS TO DETERMINE PRESSURES AND ANCHORAGE FOR THE COMMON MULLION, SEE EXAMPLES ON THIS SHEET AND SHEET 24. FOR MULTIPLE UNITS, CONSIDER ONLY TWO ADJACENT UNITS AT A TIME WHEN USING THE DESIGN PRESSURE AND ANCHORAGE TABLES. THE LOWEST DESIGN PRESSURE OF MULTIPLE MULLIONS OR FENESTRATION PRODUCTS SHALL APPLY.
- 6) WHEN FINDING YOUR SIZE IN THE MULLION TABLES, ALWAYS ROUND UP TO THE NEXT SIZE SHOWN ON THE TABLE(S).
- 7) ANCHOR EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO. WOOD BUCKS BY OTHERS, MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE STRUCTURE. ANCHORS SHALL BE COATED OR CORROSION RESISTANT AS APPROPRIATE FOR SUBSTRATE MATERIAL. DISSIMILAR MATERIALS SHALL BE PROTECTED AS REQUIRED TO PREVENT REACTIONS.
- 8) REFERENCE: TEST REPORTS: FTL-6443; ELCO ULTRACON/AGGRE-GATOR NOA'S
- 9) MULLIONS AND CLIPS HAVE BEEN DESIGNED & TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE, AND ARE APPROVED FOR IMPACT AND NON-IMPACT APPLICATIONS. MULLIONS ARE ONLY TO BE USED WITH PGT-APPROVED FENESTRATION PRODUCTS HAVING CURRENT APPROVALS.
- 10) MULLIONS ARE IN COMPLIANCE FOR USE IN THE HVHZ.
- 11) QUANTITY OF UNITS WITHIN A MULTIPLE MULLED ASSEMBLY IS UNLIMITED PROVIDED THAT THE SPAN AND OPENING WIDTH/HEIGHT OF EACH INDIVIDUAL MULLION COMPLIES WITH THE REQUIREMENTS OF THIS NOA.

INSTRUCTIONS:

- 1) DETERMINE THE DESIGN PRESSURE REQUIREMENT (LBS/FT²) FOR THE OPENING USING THE ASCE-7 STANDARD.
- 2) CHOOSE A MULLION TYPE THAT WILL FIT THE DEPTH OF THE FENESTRATION PRODUCT'S FRAME DEPTH.
- 3) REFER TO SHEET 25 TO DETERMINE IF THE WIND LOADING IS "RECTANGULAR" OR "TRIANGULAR/TRAPEZOIDAL".
- 4) FIND THE CHOSEN MULLION'S MULLION CAPACITY (LBS/FT²) FROM TABLES 1A THROUGH 16A, ON SHEETS 5 THROUGH 20 RESPECTIVELY, USING THE MULLION TYPE, LENGTH AND OPENING WIDTH OR HEIGHT (DEPENDING IF THE MULLION IS SPANNING VERTICALLY OR HORIZONTALLY). THE MULLION CAPACITY (LBS/FT²) OBTAINED SHALL MEET OR EXCEED THE DESIGN PRESSURE REQUIREMENT (LBS/FT²) FOR THE OPENING OBTAINED IN STEP 1).
- 5) FROM THE SAME TABLE USED IN STEP 4) ABOVE, FIND THE VALUE IN THE NEXT COLUMN ANCHOR CAPACITY REQUIRED (LBS). THIS VALUE REPRESENTS THE WINDLOAD TRANSFERRED TO THE SUBSTRATE BY THE ANCHORS AND MUST BE MET TO ATTAIN THE FULL MULLION CAPACITY.
- 6) FROM THE ANCHOR CAPACITY (LBS) TABLE ON THE SAME SHEET AND USING YOUR ACTUAL SUBSTRATE CONDITION (MULTIPLE ANCHOR/SUBSTRATE/ANCHOR-CLIP PATTERN MAY APPLY) SELECT AN ANCHOR CLIP PATTERN AND VERIFY THAT THE REQUIRED ANCHOR CAPACITY IS MET.
- 7) IF THE MULLION CAPACITY (LBS/FT²) OBTAINED IN THE TABLE IS HIGHER THAN THE DESIGN PRESSURE REQUIREMENT (LBS/FT²) FOR THE OPENING, YOU MAY USE THE "ANCHOR CAPACITY ADJUSTMENT FORMULA" TO OBTAIN THE LOWER ANCHOR CAPACITY REQUIRED. WITH THIS VALUE A LOWER ANCHOR CAPACITY OPTION MAY BE SELECTED FOR THE SAME SUBSTRATE
- 8) VERIFY THE DESIGN PRESSURE RATING (LBS/FT²) FOR THE FENESTRATION PRODUCT TO BE USED AND COMPARE WITH THE FINAL MULLION CAPACITY (LBS/FT²) OBTAINED FOR THE MULLION SYSTEM. THE LOWER OF THE TWO SHALL APPLY FOR THE ENTIRE MULLED FENESTRATION PRODUCT ASSEMBLY.
- 9) HIGHLIGHT OPTION USED AND TABLE VALUES USED IN A SPECIFIC APPLICATION WHEN USING THIS NOA TO APPLY FOR A PERMIT.

GENERAL NOTES.....	1
INSTRUCTIONS.....	1
ELEVATIONS.....	1
MULL TO 2X WOOD.....	2
MULL TO 1X & MASONRY.....	2
INSTALLATION NOTES.....	2
MULL TO MASONRY.....	3
MULL TO STEEL STUD.....	3
MULL TO MULL.....	3
ANCHOR SPECS.....	3
ALTERNATE CLIPS.....	4
BAY MULL INSTALLATION.....	4
1 X 2 X .125 MULL SPECS.....	5
1 X 2 X .375 MULL SPECS.....	6
1 X 2.75 X .375 MULL SPECS.....	7
1 X 2.75 X .65 MULL SPECS.....	8
1 X 3.125 X .500 MULL SPECS.....	9
1 X 4 X .125 MULL SPECS.....	10
1 X 4 X .375 TUBE MULL SPECS.....	11
1 X 4 X .375 "T" MULL SPECS.....	11
1.25 X 3.188 X .265 MULL SPECS.....	12
1.25 X 3.25 X .100 MULL SPECS.....	13
1.25 X 3.25 X .624 MULL SPECS.....	14
1.25 X 3.94 X .624 MULL SPECS.....	15
2 X 4 X .25 MULL SPECS.....	16
2 X 6 X .25 MULL SPECS.....	17
1.26 X 2.11 X .125 MULL SPECS.....	18
30° X 3.25 BAY MULL SPECS.....	19
45° X 3.25 BAY MULL SPECS.....	20
MULLION & CLIP DIMENSIONS.....	21-23
EXAMPLES 1 & 2.....	24
LOADING EXAMPLES.....	25

PGT
1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
FL CERT. OF AUTH.# 29296

IMPACT-RESISTANT ALUMINUM TUBE MULLIONS

GENERAL NOTES AND ELEVATION

Sheet: 1 of 25
Rev: B

Drawing No: 6300JR
Checked By: J. ROSOWSKI
Date: 08/29/11


Scale: N/A
Date: 10/10/14

Revised: J. ROSOWSKI


PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 16-0218
Expiration Date May 16, 2021
By Manuel Perez
Miami Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
A. LYNN MILLER, P.E.
FL P.E.# 58705

DETAIL A:
MULLION TO 2X WOOD BUCK
OR WOOD FRAMING
(OFFSET CLIP SHOWN)



DETAIL B:
MULLION ATTACHED TO 1X
WOOD BUCK AND MASONRY
(STANDARD CLIP SHOWN)



INSTALLATION NOTES:

- 1) ANCHOR EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.
- 2) QUANTITY OF ANCHORS AND MULLION SIZE SHOWN ABOVE ARE FOR PICTORIAL REPRESENTATION ONLY. BECAUSE THE ANCHOR CAPACITY IS BASED PARTLY ON THE ANCHOR TO ANCHOR DISTANCE, THE CORRECT QUANTITY AND LOCATION OF ANCHORS MUST BE FOLLOWED, REFER TO THE TABLES ON THE FOLLOWING SHEETS. FOR DETAILS A-D, EITHER THE STANDARD OR INTERIOR CLIP MAY BE USED.
- 3) ANCHOR HEAD TYPE MAY BE PANHEAD, HEXHEAD OR FLATHEAD.
- 4) WOOD BUCKS ARE OPTIONAL, SEE DETAIL C, SHEET 3.
- 5) FOR MASONRY APPLICATIONS IN MIAMI-DADE COUNTY, USE ONLY MIAMI-DADE COUNTY APPROVED ELCO ULTRACON OR ELCO 1/4" S.S. AGGREGATOR MASONRY ANCHORS.

RG
1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
FL CERT. OF AUTH. # 29296

Title: **IMPACT-RESISTANT ALUMINUM TUBE MULLIONS**

Description: **INSTALLATION INSTRUCTIONS A**

Series: **N/A** Scale: **N/A** Drawing No. **6300JR** Sheet **2 of 25**


Drawn By: **J ROSOWSKI** Date: **08/29/11** Checked By: **J ROSOWSKI** Rev: **B**

Rev. By: **J ROSOWSKI** Date: **10/10/14** Revision: **NEW MULLS TO SHEETSET**

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. **K-0218.03**
Expiration Date **May 26, 2021**
By **Manuel J. J. J.**
Miami Dade Product Control


ANTHONY LYNN MILLER
LICENSE
No. 58705
A. LYNN MILLER, P.E.
FL P.E.# 58705

DETAIL C:
MULLION DIRECTLY ATTACHED TO
MASONRY STRUCTURE
(STANDARD CLIP SHOWN)



THE OFFSET CLIP IS
RECOMMENDED FOR
FIN-FRAMED
WINDOWS, BUT MAY
ALSO BE USED FOR
OTHER FRAME TYPES.


DETAIL E:
MULLION TO MULLION
INTERSECTION
(U-CLIP)



NOTES:

- 1) MAY BE INSTALLED IN "TEE" OR "CROSS" INTERSECTIONS.
- 2) MAY BE INSTALLED HORIZONTALLY (SHOWN) OR VERTICALLY.
- 3) SEE U-CLIP DRAWINGS, SHEETS 21-23 FOR CORRESPONDING MULLION.

DETAIL D:
MULLION ATTACHED TO
STEEL STUD
(STANDARD CLIP SHOWN)




NOTES:

- 1) FOR 2X WOOD-BACKED STEEL STUDS, WOOD ANCHOR VALUES MAY BE USED.
- 2) SEE CORRESPONDING MULLION TABLES, SHEETS 5-20, FOR QUANTITY OF SCREWS.


INSTALLATION NOTES:

- 1) ANCHOR EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO.
- 2) QUANTITY OF ANCHORS AND MULLION SIZE SHOWN ABOVE ARE FOR PICTORIAL REPRESENTATION ONLY. BECAUSE THE ANCHOR CAPACITY IS BASED PARTLY ON THE ANCHOR TO ANCHOR DISTANCE, THE CORRECT QUANTITY AND LOCATION OF ANCHORS MUST BE FOLLOWED, REFER TO THE TABLES ON THE FOLLOWING SHEETS. FOR DETAILS A-D, EITHER THE STANDARD OR INTERIOR CLIP MAY BE USED.
- 3) ANCHOR HEAD TYPE MAY BE PANHEAD, HEXHEAD OR FLATHEAD.
- 4) WOOD BUCKS ARE OPTIONAL, SEE DETAIL C, SHEET 3.
- 5) FOR MASONRY APPLICATIONS IN MIAMI-DADE COUNTY, USE ONLY MIAMI-DADE COUNTY APPROVED ELCO ULTRACON OR ELCO 1/4" S.S. AGGREGATOR MASONRY ANCHORS.



Title: IMPACT-RESISTANT ALUMINUM TUBE MULLIONS		Sheet: 3 of 25	Rev: B
Description: INSTALLATION INSTRUCTIONS B		Drawing No. 6300JR	Checked By: Date:
Series: N/A		Scale: N/A	Date: 08/29/11
Drawn By: J. ROSOWSKI		Rev. By: J. ROSOWSKI	Revision: 10/10/14
NEW MULLS TO SHEETSET			




PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 16-0218-03
Expiration Date 12/31/2021
By *Manuel*
Miami Dade Product Control



DETAIL F:
FIELD-MODIFIED MULLION CLIP
(F-CLIP)

DETAIL G:
ANGLE MULLION CLIP
(ANGLE CLIP)

DETAIL H:
BAY MULLION INSTALLATION
(ANGLE CLIP)




NOTES FOR INSTALLATION OPTIONS F:

- 1) DETAIL IS NOT APPLICABLE FOR THE BAY OR 1.26\" X 2.11\" X .125\" MULLION.
- 2) SEE TABLES 1B-13B FOR ANCHOR QUANTITIES AND SHEETS 21-23 FOR HOLE LOCATIONS.
- 3) THE 2X5 CLIP IS NOT SUITABLE FOR THIS APPLICATION.

NOTES FOR INSTALLATION OPTION G & H:

- 1) USE 2 ANGLE CLIPS PER MULLION END. CLIPS MUST BE INSERTED INSIDE OF MULLION.
- 2) DETAIL G: SEE TABLES 1B-14B FOR ANCHOR QUANTITIES AND SHEETS 21-23 FOR HOLE LOCATIONS.
- 3) DETAIL H: SEE TABLES 15B OR 16B FOR ANCHOR QUANTITIES AND SHEET 22 FOR HOLE LOCATIONS.



IMPACT-RESISTANT ALUMINUM TUBE MULLIONS		INSTALLATION INSTRUCTIONS C	
Series:	N/A	Drawing No.	6300JR
Drawn By:	J ROSOWSKI	Checked By:	B
Rev. By:	J ROSOWSKI	Date:	08/29/11
10/10/14 NEW MULLS TO SHEETSET		Sheet:	4 of 25

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 16-0218-03
Expiration Date May 26, 2021
By *Manuel J. J. J.*
Miami Dade Product Control




TABLE 1A

1 x 2 x .125 Alum. Tube Mullion		Mullion Capacity Table (lbs/ft ²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading	
Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)			
Mull Length	42 in	111.9	408	129.5	332	93.2	408	115.5	325	79.9	408	107.8	321	69.9	408	104.4	319	62.1	408	104.0	319	55.9	408	104.0	319	46.6	408	104.0	319	38.9	408	104.0	319	35.0	408	104.0	319
	48 in	74.9	312	83.8	258	62.4	312	73.4	252	53.5	312	67.0	248	46.8	312	63.2	246	41.6	312	61.3	244	37.5	312	61.0	244	31.2	312	61.0	244	26.8	312	61.0	244	23.4	312	61.0	244
	50.625 in	63.9	281	70.6	234	53.2	281	61.5	228	45.6	281	55.7	224	39.9	281	52.1	222	35.5	281	50.1	220	31.9	281	49.3	219	26.6	281	49.3	219	22.8	281	49.3	219	20.0	281	49.3	219
	54 in	52.6	247	57.5	207	43.9	247	49.8	202	37.6	247	44.8	199	32.9	247	41.5	196	29.2	247	39.4	194	26.3	247	38.4	193	21.9	247	38.1	193	18.8	247	38.1	193	16.4	247	38.1	193
	60 in	38.4	200	41.2	170	32.0	200	35.4	168	27.4	200	31.5	163	24.0	200	28.9	160	21.3	200	27.1	159	19.2	200	25.9	157	16.0	200	25.0	156								
	63 in	33.1	181	35.3	155	27.6	181	30.3	152	23.7	181	26.9	149	20.7	181	24.5	146	18.4	181	22.8	144	16.6	181	21.7	143												
	66 in	28.8	165	30.6	142	24.0	165	26.1	139	20.6	165	23.1	136	18.0	165	21.0	134																				
	72 in	22.2	139	23.3	120	18.5	139	19.9	118	15.9	139	17.5	116																								
	76 in	18.9	125	19.7	109	15.7	125	16.8	107																												
	78 in	17.5	118	18.2	104																																

TABLE 1B

Anchor Clip Patterns		Anchor Capacity Table (lbs)															
		Substrate:															
		2.7k Concrete								3.5k Conc.				Hollow CMU			
		Anchor Type:		3/16" Ecco Ultracon		1/4" Ecco Ultracon		5/16" Ecco Ultracon		3/16" Ecco Ultracon		1/4" Ecco Ultracon		1/4" SS Ecco AggreGator	5/16" Ecco Ultracon	1/4" SS Ecco AggreGator	PT Wood
		Edge Distance (in):		1"	2-1/2"	1"	2-1/2"	3-1/8"		1"	2-1/2"	1"	2-1/2"	2"	3-1/8"	2"	#10 Steel Screw (G5)
		Embedment (in):		1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"		1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-3/8"	#12 Steel Screw (G5)
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1):				390 lbs	390 lbs	450 lbs	890 lbs	1644 lbs		270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	664 lbs	946 lbs	341 lbs
4 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 2):				480 lbs	700 lbs	N/A	N/A	N/A		380 lbs	N/A	N/A	N/A	N/A	N/A	682 lbs	885 lbs
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3):				780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs		540 lbs	560 lbs	N/A	760 lbs	748 lbs	880 lbs	1892 lbs	682 lbs
2 Anchors @ 0.45" Min. O.C. / U-Clip, into .125" Alum. (Fig. 4):				N/A	N/A	N/A	N/A	N/A		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
1 Anchor / F-Clip (Fig. 5):				195 lbs	195 lbs	225 lbs	445 lbs	822 lbs		135 lbs	140 lbs	177 lbs	370 lbs	187 lbs	332 lbs	473 lbs	170 lbs
2 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 6):				240 lbs	350 lbs	N/A	N/A	N/A		N/A	190 lbs	N/A	N/A	N/A	N/A	341 lbs	442 lbs

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP.





TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.



ANCHOR CAPACITY ADJUSTMENT FORMULA:

$$(DP_{REQ}) \times \left(\frac{ANCHOR CAP. FROM TABLE}{MULLION CAP. FROM TABLE} \right) = ANCHOR CAP. REQ.$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.

PRODUCT REVISED as complying with the Florida Building Code

Acceptance No. 16-0218-03

Expiration Date 12/26/2021

By *Manuel Perez*

Miami Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
STATE OF FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
FL P.E.# 58705


TABLE 2A

TABLE 2A																																					
Mullion Capacity Table (lbs/ft ²)																																					
1 x 2 x .375 Alum. Tube Mullion		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading					
		Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)				
Mull Length	42 in	170.0	620	170.0	435	151.3	662	170.0	478	129.7	662	170.0	506	113.5	662	169.5	518	100.9	662	168.9	517	90.8	662	168.9	517	75.7	662	168.9	517	64.9	662	168.9	517	58.7	662	168.9	517
	48 in	121.6	507	136.0	419	101.4	507	119.2	410	86.9	507	108.7	403	76.0	507	102.6	399	67.6	507	99.6	397	60.8	507	99.0	396	50.7	507	99.0	396	43.4	507	99.0	396	38.0	507	99.0	396
	50.625 in	103.7	456	114.6	379	86.4	456	99.9	371	74.1	456	90.5	364	64.8	456	84.6	360	57.6	456	81.3	357	61.8	456	80.0	356	43.2	456	80.0	356	37.0	456	80.0	356	32.4	456	80.0	356
	54 in	85.4	400	93.3	336	71.2	400	80.9	328	61.0	400	72.7	322	53.4	400	67.3	318	47.5	400	64.0	315	42.7	400	62.3	314	35.6	400	61.8	313	30.5	400	61.8	313	26.7	400	61.8	313
	60 in	62.3	324	66.9	276	51.9	324	57.5	270	44.5	324	51.2	264	38.9	324	46.9	260	34.6	324	43.9	257	31.1	324	42.0	255	26.0	324	40.5	253	22.2	324	40.5	253	19.5	324	40.5	253
	63 in	53.8	294	57.4	252	44.8	294	49.2	246	38.4	294	43.6	241	33.6	294	39.8	237	29.9	294	37.1	234	26.9	294	35.2	232	22.4	294	33.5	230	19.2	294	33.4	230	16.8	294	33.4	230
	66 in	46.8	268	49.6	230	39.0	268	42.4	225	33.4	268	37.5	221	29.2	268	34.1	218	26.0	268	31.6	215	23.4	268	29.8	212	19.5	268	28.0	210	16.7	268	27.7	209	14.6	268	27.7	209
	72 in	36.0	225	37.9	196	30.0	225	32.2	191	25.7	225	28.4	188	22.5	225	25.6	185	20.0	225	23.6	182	18.0	225	22.1	180	15.0	225	20.3	177	12.9	225	19.6	176	11.3	225	19.6	176
	76 in	30.6	202	32.0	177	25.5	202	27.2	173	21.9	202	23.9	170	19.2	202	21.5	167	17.0	202	19.7	165	15.3	202	18.4	163	12.8	202	16.7	160	10.9	202	15.9	158	9.6	202	15.8	158
	78 in	28.3	192	29.6	168	23.6	192	25.1	165	20.2	192	22.0	162	17.7	192	19.7	159	15.7	192	18.1	157	14.2	192	16.8	155	11.8	192	15.2	152	10.1	192	14.4	150	8.9	192	14.2	150
90 in	18.5	144	19.0	128	15.4	144	16.1	126																													
96 in	15.2	127	15.6	113																																	


TABLE 2B

Anchor Clip Patterns		Anchor Capacity Table (lbs)													
		Substrate:		2.7k Concrete				3.5k Conc.		Hollow CMU				Filled CMU	
		Anchor Type:		3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon		3/16" Elco Ultracon		1/4" Elco Ultracon		1/4" SS Elco AggreGator	
		Edge Distance (in):	Embedment (in):	1"	2-1/2"	1"	2-1/2"	1"	2-1/2"	1"	2-1/2"	1"	2-1/2"	2"	3-1/8"
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1):		1-3/4"	1-3/4"	390 lbs	390 lbs	450 lbs	890 lbs	1644 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	664 lbs	946 lbs
4 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 2):		1-3/4"	1-3/4"	480 lbs	700 lbs	N/A	N/A	N/A	N/A	380 lbs	N/A	N/A	N/A	N/A	341 lbs
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3):		1-3/4"	1-3/4"	780 lbs	780 lbs	880 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	748 lbs	880 lbs	1892 lbs
2 Anchors @ 0.45" Min. O.C. / U-Clip, into .125" Alum. (Fig. 4):		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
1 Anchor / F-Clip (Fig. 5):		N/A	N/A	195 lbs	195 lbs	225 lbs	445 lbs	822 lbs	135 lbs	140 lbs	177 lbs	370 lbs	187 lbs	332 lbs	473 lbs
2 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 6):		N/A	N/A	240 lbs	350 lbs	N/A	N/A	N/A	N/A	190 lbs	N/A	N/A	N/A	N/A	341 lbs

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP.



- TABLE NOTES:
- SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
 - LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
 - MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
 - SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.



ANCHOR CAPACITY ADJUSTMENT FORMULA:

$$(DP_{REQ}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP. REQ.}$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.

PRODUCT REVISED as complying with the Florida Building Code

Acceptance No. 16-0218-03

Expiration Date May 26, 2021

By Mameel P. Miller

Miami Made Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
4/8/16
STATE OF FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
FL P.E.# 58705

TABLE 3A

1 x 2.75 x .375 Alum. Tube Mullion		Mullion Capacity Table (lbs/ft ²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading	
Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)			
Mull Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	508	170.0	992	170.0	518	170.0	1116	170.0	521	170.0	1240	170.0	521	148.7	1301	170.0	521	127.5	1301	170.0	521	111.5	1301	170.0	521
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	661	151.8	1139	170.0	677	136.6	1139	170.0	680	113.9	1139	170.0	680	97.6	1139	170.0	680	85.4	1139	170.0	680
	50.625 in	170.0	747	170.0	563	170.0	896	170.0	631	167.8	1032	170.0	684	146.8	1032	170.0	723	130.5	1032	170.0	747	117.4	1032	170.0	756	97.9	1032	170.0	756	83.9	1032	170.0	756	73.4	1032	170.0	756
	54 in	170.0	797	170.0	612	161.3	907	170.0	691	138.2	907	164.7	730	120.9	907	152.5	720	107.5	907	145.0	714	96.8	907	141.1	710	80.6	907	140.0	709	69.1	907	140.0	709	60.5	907	140.0	709
	60 in	141.1	735	151.5	625	117.6	735	130.3	611	100.8	735	116.0	599	88.2	735	106.2	590	78.4	735	89.5	583	70.5	735	95.1	578	58.8	735	91.8	574	50.4	735	91.8	574	44.1	735	91.8	574
	63 in	121.9	666	130.0	570	101.6	666	111.5	557	87.0	666	98.9	547	76.2	666	90.1	536	67.7	666	83.9	531	60.9	666	79.8	526	50.8	666	75.8	521	43.5	666	75.6	521	38.1	666	75.6	521
	66 in	106.0	607	112.4	522	88.3	607	96.1	511	75.7	607	85.0	501	66.2	607	77.1	493	58.9	607	71.5	486	53.0	607	67.6	481	44.2	607	63.4	476	37.9	607	62.7	474	33.1	607	62.7	474
	72 in	81.6	510	85.8	443	68.0	510	73.0	434	58.3	510	64.3	426	51.0	510	57.9	419	45.4	510	53.3	413	40.8	510	50.0	408	34.0	510	45.9	402	29.2	510	44.4	399	25.5	510	44.3	399
	76 in	69.4	458	72.5	400	57.8	458	61.7	392	49.6	458	54.1	385	43.4	458	48.6	378	38.6	458	44.6	373	34.7	458	41.6	368	28.9	458	37.7	362	24.8	458	36.0	359	21.7	458	35.7	358
	78 in	64.2	435	67.0	381	53.5	435	56.6	373	45.9	435	49.8	366	40.1	435	44.7	360	35.7	435	40.9	355	32.1	435	38.1	351	26.8	435	34.4	344	22.9	435	32.6	341	20.1	435	32.2	340
	90 in	41.8	327	43.1	290	34.8	327	36.4	285	29.9	327	31.8	280	26.1	327	28.3	275	23.2	327	25.7	271	20.9	327	23.7	268	17.4	327	21.0	262	14.9	327	19.3	258				
	96 in	34.4	287	35.4	257	28.7	287	29.9	252	24.6	287	26.0	248	21.5	287	23.1	244	19.1	287	20.9	240	17.2	287	19.3	237	14.4	287	16.9	232								
108 in	24.2	227	24.7	205	20.2	227	20.8	201	17.3	227	18.0	198	15.1	227	16.0	195																					
111 in	22.3	215	22.7	194	18.6	215	19.1	191	15.9	215	16.6	188																									
120 in	17.6	184	17.9	167																																	

TABLE 3B

Anchor Clip Patterns		Anchor Capacity Table (lbs)																	
		Substrate:	2.7k Concrete				3.5k Conc.	Hollow CMU				Filled CMU	PT Wood		Metal				
			Anchor Type:		3/16" Elco Ultracon		1/4" Elco Ultracon	5/16" Elco Ultracon	3/16" Elco Ultracon		1/4" Elco Ultracon	1/4" SS Elco AggreGator	5/16" Elco Ultracon	1/4" SS Elco AggreGator	#10 Steel Screw (G5)	#12 Steel Screw (G5)	#12 Steel Screw (G5)		
					1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	2"	3-1/8"	2"	0.48"	0.54"	0.324"
					Edge Distance (in):	1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	2"	3-1/8"	2"	0.48"	0.54"
Embedment (in):	1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	2"	1-3/8"	1-3/8"	varies				
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1):		390 lbs	390 lbs	450 lbs	890 lbs	1644 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	664 lbs	946 lbs	341 lbs	442 lbs	560 lbs			
4 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 2):		480 lbs	700 lbs	N/A	N/A	N/A	N/A	380 lbs	N/A	N/A	N/A	N/A	N/A	682 lbs	885 lbs	1120 lbs			
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3):		780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	746 lbs	880 lbs	1892 lbs	682 lbs	885 lbs	1120 lbs			
2 Anchors @ 0.45" Min. O.C. / U-Clip, into .125" Alum. (Fig. 4):		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	715 lbs			
1 Anchor / F-Clip (Fig. 5):		195 lbs	195 lbs	225 lbs	445 lbs	822 lbs	135 lbs	140 lbs	177 lbs	370 lbs	187 lbs	332 lbs	473 lbs	170 lbs	221 lbs	280 lbs			
2 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 6):		240 lbs	350 lbs	N/A	N/A	N/A	N/A	190 lbs	N/A	N/A	N/A	N/A	N/A	341 lbs	442 lbs	560 lbs			

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP. CIRCLED VALUES ARE USED IN THE EXAMPLE ON SHEET 24.





TABLE NOTES:

1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.

2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.

3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.

4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.



ANCHOR CAPACITY ADJUSTMENT FORMULA:

$(DP_{REQ}) \times \left(\frac{ANCHOR CAP. FROM TABLE}{MULLION CAP. FROM TABLE} \right) = ANCHOR CAP. REQ.$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.

PRODUCT REVISED as complying with the Florida Building Code Acceptance No. 16-0218.03 Expiration Date May 26, 2021

By *Anthony Lynn Miller* Miami Dade Product Control

ANTHONY LYNN MILLER LICENSE No. 58705 9/8/16 STATE OF FLORIDA PROFESSIONAL ENGINEER A. LYNN MILLER, P.E. FL P.E.# 58705

1070 TECHNOLOGY DRIVE N. VENICE, FL 34275 P.O. BOX 1529 NOKOMIS, FL 34274 FL CERT. OF AUTH.# 29296

1 X 2.75 X .375 MULL SPECS

6300JR

Scale: N/A

Drawn By: J. ROSOWSKI

Checked By: J. ROSOWSKI

Date: 08/29/11

Date: 10/10/14

Revision: NEW MULLS TO SHEETSET

Sheet: 7 of 25

Rev: B

TABLE 4A

1 x 2.75 x .650 Alum. Tube Mullion		Mullion Capacity Table (lbs/ft ²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading					
Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft ²)		Anchor Capacity Required (lbs)							
Mull Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	506	170.0	992	170.0	519	170.0	1116	170.0	521	170.0	1240	170.0	521	170.0	1488	170.0	521	158.7	1620	170.0	521	138.8	1620	170.0	521
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	661	170.0	1275	170.0	677	170.0	1417	170.0	680	170.0	1417	170.0	680	121.5	1417	170.0	680	106.3	1417	170.0	680
	50.625 in	170.0	747	170.0	563	170.0	896	170.0	631	170.0	1046	170.0	684	170.0	1195	170.0	723	162.6	1286	170.0	747	146.3	1286	170.0	756	121.9	1286	170.0	758	104.5	1286	170.0	756	91.4	1286	170.0	756
	54 in	170.0	797	170.0	612	170.0	956	170.0	681	170.0	1116	170.0	754	150.7	1130	170.0	803	133.9	1130	170.0	837	120.6	1130	170.0	856	100.5	1130	170.0	861	86.1	1130	170.0	861	75.3	1130	170.0	861
	60 in	170.0	885	170.0	701	146.5	915	162.3	781	125.5	915	144.5	746	109.9	915	132.3	735	97.8	915	123.9	726	87.9	915	116.5	720	73.2	915	114.4	715	62.8	915	114.4	715	54.9	915	114.4	715
	63 in	151.8	830	161.9	710	126.5	830	138.9	694	108.5	830	123.2	681	94.9	830	112.2	670	84.4	830	104.6	662	75.9	830	99.4	656	63.3	830	94.5	649	54.2	830	94.1	649	47.4	830	94.1	649
	66 in	132.1	757	140.0	650	110.0	757	119.8	636	94.3	757	105.9	624	82.5	757	96.1	614	73.4	757	89.1	606	66.0	757	84.2	600	55.0	757	79.0	593	47.2	757	78.2	591	41.3	757	78.2	591
	72 in	101.7	636	106.8	552	84.8	636	91.0	540	72.7	636	80.1	530	63.6	636	72.2	521	56.5	636	66.5	514	50.9	636	62.3	508	42.4	636	57.2	500	36.3	636	55.3	497	31.8	636	55.2	497
	76 in	88.5	571	90.4	498	72.1	571	76.8	468	61.8	571	67.4	479	54.1	571	60.6	471	48.0	571	55.5	464	43.2	571	51.8	459	36.0	571	47.0	451	30.9	571	44.8	447	27.0	571	44.5	446
	78 in	80.0	542	83.4	474	66.7	542	70.8	485	57.1	542	62.1	456	50.0	542	55.7	449	44.4	542	51.0	442	40.0	542	47.5	437	33.3	542	42.9	429	28.6	542	40.6	425	25.0	542	40.1	423
	90 in	52.1	407	53.7	361	43.4	407	45.4	355	37.2	407	39.8	349	32.5	407	35.3	343	28.9	407	32.1	338	26.0	407	29.6	334	21.7	407	26.1	327	18.6	407	24.1	322	16.3	407		319
	96 in	42.9	358	44.1	320	35.8	358	37.2	314	30.7	358	32.4	309	26.8	358	28.8	304	23.8	358	26.1	300	21.5	358	24.0	296	17.9	358	21.0	289	15.3	358	19.2	284				
	108 in	30.1	283	30.8	255	25.1	283	25.9	251	21.5	283	22.5	247	18.8	283	19.9	244	16.7	283	18.0	240	15.1	283	16.5	237												
	111 in	27.8	267	28.3	242	23.1	267	23.8	238	19.8	267	20.6	235	17.3	267	18.3	231	15.4	267	16.5	228																
	120 in	22.0	229	22.3	209	18.3	229	18.8	205	15.7	229	16.2	202																								

TABLE 4B

Anchor Capacity Table (lbs)																		
Anchor Clip Patterns	Substrate:	2.7k Concrete				3.5k Conc.	Hollow CMU				Filled CMU		PT Wood		Metal			
	Anchor Type:	3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon	3/16" Elco Ultracon		1/4" Elco Ultracon		1/4" SS Elco AggreGator	5/16" Elco Ultracon	1/4" SS Elco AggreGator	#10 Steel Screw (G5)	#12 Steel Screw (G5)	#12 Steel Screw (G5)		
	Edge Distance (in):	1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	2"	3-1/8"	2"	0.48"	0.54"	0.324"		
	Embedment (in):	1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	2"	1-3/8"	1-3/8"	varies		
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1):		390 lbs	390 lbs	450 lbs	890 lbs	1644 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	664 lbs	946 lbs	341 lbs	442 lbs	560 lbs		
4 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 2):		480 lbs	700 lbs	N/A	N/A	N/A	N/A	380 lbs	N/A	N/A	N/A	N/A	N/A	682 lbs	885 lbs	1120 lbs		
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3):		760 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	748 lbs	880 lbs	1892 lbs	682 lbs	885 lbs	1120 lbs		
2 Anchors @ 0.45" Min. O.C. / U-Clip, into .125" Alum. (Fig. 4):		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	715 lbs		
1 Anchor / F-Clip (Fig. 5):		195 lbs	195 lbs	225 lbs	445 lbs	822 lbs	135 lbs	140 lbs	177 lbs	370 lbs	187 lbs	332 lbs	473 lbs	170 lbs	221 lbs	280 lbs		
2 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 6):		240 lbs	350 lbs	N/A	N/A	N/A	N/A	190 lbs	N/A	N/A	N/A	N/A	N/A	341 lbs	442 lbs	560 lbs		

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP. CIRCLED VALUES ARE USED IN THE EXAMPLE ON SHEET 24.





TABLE NOTES:

- SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.



ANCHOR CAPACITY ADJUSTMENT FORMULA:

$$(DP_{REQ}) \times \left(\frac{ANCHOR CAP. FROM TABLE}{MULLION CAP. FROM TABLE} \right) = ANCHOR CAP. REQ.$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.

PRODUCT REVISED as complying with the Florida Building Code 16-0218.03
Acceptance No. 16-0218.03
Expiration Date May 26, 2021
By *Manuel Perez*
Miami/Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
4/8/16
STATE OF FLORIDA
PROFESSIONAL ENGINEER

A. LYNN MILLER, P.E.
FL P.E.# 58705

PG
1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1523
NOKOMIS, FL 34274
FL CERT. OF AUTH.# 29296

Title: IMPACT-RESISTANT ALUMINUM TUBE MULLIONS
Description: 1 X 2.75 X .650 MULL SPECS
Series: N/A
Drawing No: 6300JR
Scale: N/A
Checked By: J. ROSOWSKI
Date: 08/29/11
Rev. By: J. ROSOWSKI
Date: 10/10/14
Revision: NEW MULLS TO SHEETSET

Sheet: 8 of 25
Rev: B

TABLE 5A

1" x 3.125" x .500" Alum Tube Mull		Mullion Capacity Table (lbs/ft ²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				80 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading					
Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)			
Mull Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	888	170.0	506	170.0	992	170.0	519	170.0	1116	170.0	521	170.0	1240	170.0	521	170.0	1488	170.0	521	170.0	1735	170.0	521	154.4	1802	170.0	521
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	681	170.0	1275	170.0	677	170.0	1417	170.0	680	157.7	1577	170.0	680	135.1	1577	170.0	680	118.2	1577	170.0	680
	50.625 in	170.0	747	170.0	563	170.0	898	170.0	631	170.0	1046	170.0	684	170.0	1185	170.0	723	170.0	1345	170.0	747	170.0	1484	170.0	758	141.7	1495	170.0	758	121.5	1495	170.0	758	106.3	1495	170.0	758
	54 in	170.0	797	170.0	612	170.0	958	170.0	691	170.0	1118	170.0	754	170.0	1275	170.0	803	186.1	1401	170.0	837	149.5	1401	170.0	858	124.6	1401	170.0	861	106.8	1401	170.0	861	93.4	1401	170.0	861
	60 in	170.0	885	170.0	701	170.0	1083	170.0	797	158.5	1156	170.0	878	138.7	1156	167.0	928	123.3	1156	156.5	917	111.0	1156	149.7	910	92.5	1156	144.5	903	79.3	1156	144.5	903	69.4	1156	144.5	903
	63 in	170.0	930	170.0	745	159.8	1049	170.0	850	137.0	1049	155.5	880	119.8	1049	141.7	846	106.5	1049	132.0	836	95.9	1049	125.5	828	79.9	1049	119.3	820	68.5	1049	118.9	819	59.9	1049	118.9	819
	66 in	166.8	955	170.0	789	139.0	955	151.3	804	119.1	955	133.7	788	104.2	955	121.4	775	92.8	955	112.6	765	83.4	955	106.4	757	69.5	955	99.8	749	59.8	955	98.7	748	52.1	955	98.7	748
	72 in	128.5	803	134.9	697	107.0	803	114.9	682	91.8	803	101.1	670	80.3	803	91.2	659	71.4	803	83.9	649	64.2	803	78.6	642	53.5	803	72.2	632	45.9	803	69.8	628	40.1	803	69.7	627
	78 in	109.2	721	114.1	629	91.0	721	97.0	616	78.0	721	85.1	605	68.3	721	76.5	595	60.7	721	70.1	588	54.6	721	65.4	579	45.5	721	59.4	569	39.0	721	56.6	564	34.1	721	56.1	563
	78 in	101.0	684	105.4	599	84.2	684	89.4	587	72.2	684	78.4	576	63.1	684	70.4	567	58.1	684	64.4	558	50.5	684	59.9	551	42.1	684	54.1	541	36.1	684	51.3	536	31.6	684	50.6	534
	90 in	85.8	514	87.9	456	54.8	514	57.3	448	47.0	514	50.0	440	41.1	514	44.6	433	38.5	514	40.5	427	32.9	514	37.3	421	27.4	514	33.0	412	23.5	514	30.4	406	20.8	514	29.0	403
	96 in	54.2	452	55.7	404	45.2	452	47.0	396	38.7	452	40.9	390	33.9	452	36.4	384	30.1	452	32.9	378	27.1	452	30.3	373	22.6	452	26.6	385	19.4	452	24.2	359	16.9	452	22.8	355
	108 in	38.1	357	38.9	322	31.7	357	32.7	317	27.2	357	28.4	312	23.8	357	25.2	308	21.1	357	22.7	303	19.0	357	20.8	299	15.9	357	18.0	293	13.8	357	16.2	287	11.9	357	15.0	283
	111 in	35.1	336	35.8	306	29.2	336	30.1	301	25.0	336	26.1	296	21.9	336	23.1	292	19.5	336	20.8	288	17.5	336	19.0	284	14.6	336	16.5	278	12.5	336	14.8	273	11.0	336	13.6	269
	120 in	27.7	289	28.2	263	23.1	289	23.7	259	19.8	289	20.5	256	17.3	289	18.1	252	15.4	289	16.3	249	13.9	289	14.9	246	11.6	289	12.8	240	9.9	289	11.4	236	8.7	289	10.4	232

TABLE 5B

Anchor Clip Patterns		Anchor Capacity Table (lbs)																													
		Substrate:		2.7k Concrete				3.5k Conc.	Hollow CMU				Filled CMU	PT Wood		Metal															
				3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon	3/16" Elco Ultracon		1/4" Elco Ultracon		1/4" SS Elco AggreGator	5/16" Elco Ultracon	1/4" SS Elco AggreGator	#10 Steel Screw (G5)	#12 Steel Screw (G5)	#12 Steel Screw (G5)													
		Anchor Type:																													
		Edge Distance (in):		1"		2-1/2"		1"	2-1/2"		3-1/8"		1"		2-1/2"		1"	2-1/2"		2"	3-1/8"		0.48"	0.54"	0.324"						
Embedment (in):		1-3/4"		1-3/4"		1-3/4"	1-3/4"		2"	1-1/4"		1-1/4"		1-1/4"	1-1/4"		1-1/4"	1-1/4"		2"	1-3/8"		1-3/8"	varies							
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1)		390 lbs		390 lbs		450 lbs		890 lbs		1644 lbs		270 lbs		280 lbs		354 lbs		740 lbs		374 lbs		664 lbs		946 lbs		341 lbs		442 lbs		560 lbs	
4 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 2)		480 lbs		700 lbs		N/A		N/A		N/A		N/A		380 lbs		N/A		N/A		N/A		N/A		N/A		682 lbs		885 lbs		1120 lbs	
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3)		780 lbs		780 lbs		680 lbs		1560 lbs		1896 lbs		540 lbs		560 lbs		N/A		760 lbs		748 lbs		880 lbs		1892 lbs		682 lbs		885 lbs		1120 lbs	
3 Anchors @ 0.45" Min. O.C. / U-Clip, Into .125" Alum. (Fig. 4)		N/A		N/A		N/A		N/A		N/A		N/A		N/A		N/A		N/A		N/A		N/A		N/A		N/A		N/A		1073 lbs	
1 Anchor / F-Clip (Fig. 5)		195 lbs		195 lbs		225 lbs		445 lbs		822 lbs		135 lbs		140 lbs		177 lbs		370 lbs		187 lbs		332 lbs		473 lbs		170 lbs		221 lbs		280 lbs	
2 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 6)		240 lbs		350 lbs		N/A		N/A		N/A		N/A		180 lbs		N/A		N/A		N/A		N/A		N/A		341 lbs		442 lbs		560 lbs	

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP.

FIGURE 1:



FIGURE 2:





FIGURE 3:



ANGLE CLIP MUST BE USED IN PAIRS.

FIGURE 4:




FIGURE 5:




FIGURE 6:




TABLE NOTES:

1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.

2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.


3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.

4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.

ANCHOR CAPACITY ADJUSTMENT FORMULA:

$$(DP_{REQ}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP. REQ.}$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 16-0218.03
Expiration Date 12/26/2021
By *Manuel Perez*
Miami Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
4/8/16
STATE OF FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
FL P.E.# 58705

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
FL CERT. OF AUTH.# 29296

IMPACT-RESISTANT ALUMINUM TUBE MULLIONS
Description: 1 X 3.125 X .5 MULL SPECS
Drawing No. 6300JR
Scale: N/A
Date: 08/29/11
Checked By: J. ROSOWSKI
Date: 10/10/14
Revision: 10/10/14 NEW MULLS TO SHEETSET


TABLE 6A

1 x 4 x .125 Alum. Tube Mullion		Mullion Capacity Table (lbs/ft ²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading					
Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)						
Mull Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	888	170.0	506	170.0	992	170.0	519	170.0	1116	170.0	521	170.0	1488	170.0	521	145.8	1489	170.0	521	127.6	1489	170.0	521				
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	661	170.0	1275	170.0	677	156.3	1303	170.0	680	130.3	1303	170.0	680	97.7	1303	170.0	680				
	50.825 in	170.0	747	170.0	583	170.0	896	170.0	631	170.0	1046	170.0	684	170.0	1195	170.0	723	156.1	1235	170.0	747	140.5	1235	170.0	756	117.1	1235	170.0	766	100.4	1235	170.0	756				
	54 in	170.0	797	170.0	612	170.0	956	170.0	691	170.0	1116	170.0	754	154.4	1158	170.0	803	137.2	1158	170.0	837	123.5	1158	170.0	856	102.9	1158	170.0	861	77.2	1158	170.0	861				
	60 in	170.0	885	170.0	701	166.7	1042	170.0	797	142.9	1042	161.1	832	125.1	1042	148.7	815	111.2	1042	136.8	801	100.0	1042	130.2	791	83.4	1042	125.1	782	71.5	1042	125.1	782				
	63 in	170.0	930	170.0	745	151.2	992	163.6	818	129.6	992	144.4	799	113.4	992	131.0	762	100.8	992	121.4	768	90.7	992	114.8	758	75.6	992	108.4	745	64.8	992	108.0	744				
	66 in	165.4	947	170.0	789	137.8	947	148.0	786	118.1	947	130.3	768	103.4	947	117.7	752	91.8	947	108.7	738	82.7	947	102.2	727	68.9	947	95.1	713	59.1	947	94.0	711				
	72 in	135.9	849	142.7	737	113.2	849	121.6	722	97.0	849	106.9	708	84.9	849	96.4	696	75.5	849	88.7	686	67.9	849	82.7	675	56.6	849	75.3	659	48.5	849	72.5	652				
	76 in	115.5	762	120.7	665	96.3	762	102.6	652	82.5	762	90.0	640	72.2	762	80.9	629	64.2	762	74.2	620	57.8	762	69.2	613	48.1	762	62.8	602	41.3	762	59.9	597				
	78 in	106.9	724	111.4	634	89.0	724	94.6	621	76.3	724	82.9	609	66.8	724	74.4	599	59.4	724	68.1	591	53.4	724	63.4	583	44.5	724	57.3	573	38.2	724	54.3	667				
	90 in	89.6	543	71.8	483	58.0	543	60.7	474	49.7	543	52.9	466	43.5	543	47.1	458	38.6	543	42.8	452	34.8	543	39.5	446	29.0	543	34.9	436	24.8	543	32.1	430				
	96 in	57.3	478	58.9	427	47.8	478	49.7	419	40.9	478	43.2	412	35.8	478	38.5	406	31.8	478	34.8	400	28.7	478	32.0	395	23.9	478	28.1	386	20.5	478	25.6	380				
	108 in	40.3	377	41.1	341	33.5	377	34.6	335	28.8	377	30.0	330	25.2	377	26.6	325	22.4	377	24.0	321	20.1	377	22.0	317	16.8	377	19.0	310	14.4	377	17.1	304				
	111 in	37.1	357	37.8	323	30.9	357	31.8	318	26.5	357	27.6	313	23.2	357	24.4	309	20.6	357	22.0	305	18.5	357	20.1	301	15.4	357	17.4	294								
	120 in	29.3	306	29.8	279	24.5	306	25.1	274	21.0	306	21.7	270	18.3	306	19.2	267	16.3	306	17.3	263																
144 in	17.0	212	17.2	196																																	

TABLE 6B

Anchor Clip Patterns		Anchor Capacity Table (lbs)											
		Substrate:		2.7k Concrete				3.5k Conc.		Hollow CMU			
		Anchor Type:		3/16" Eiko Ultracon		1/4" Eiko Ultracon		5/16" Eiko Ultracon		3/16" Eiko Ultracon		1/4" Eiko Ultracon	
		Edge Distance (in):		1"	2-1/2"	1"	2-1/2"	3-1/8"		1"	2-1/2"	1"	2-1/2"
		Embedment (in):		1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"		1-1/4"	1-1/4"	1-1/4"	1-1/4"
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1&2):				390 lbs	390 lbs	450 lbs	890 lbs	1644 lbs		270 lbs	280 lbs	354 lbs	740 lbs
4 Anchors @ 2.25" Min. O.C. / Standard (or Offset) Clip (Fig. 3):				700 lbs	700 lbs	580 lbs	1410 lbs	952 lbs	N/A	560 lbs	N/A	630 lbs	N/A
8 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 4):				960 lbs	1400 lbs	N/A	N/A	N/A	N/A	760 lbs	N/A	N/A	N/A
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 5):				780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs		540 lbs	560 lbs	N/A	748 lbs
6 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 6):				1170 lbs	1170 lbs	1020 lbs	2340 lbs	2844 lbs		810 lbs	840 lbs	N/A	1140 lbs
4 Anchors @ 0.45" Min. O.C. / U-Clip, Into .125" Alum. (Fig. 7):				N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
2 Anchors @ 2.25" Min. O.C. / F-Clip (Fig. 8):				350 lbs	350 lbs	290 lbs	705 lbs	476 lbs	N/A	280 lbs	N/A	315 lbs	N/A
4 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 9):				480 lbs	700 lbs	N/A	N/A	N/A	N/A	380 lbs	N/A	N/A	N/A

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP.



ANGLE CLIP (FIGURES 5&6) MUST BE USED IN PAIRS.


TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.

ANCHOR CAPACITY ADJUSTMENT FORMULA:

$(DP_{REQ}) \times \left(\frac{ANCHOR CAP. FROM TABLE}{MULLION CAP. FROM TABLE} \right) = ANCHOR CAP. REQ.$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED as complying with the Florida Building Code Acceptance No. 16-0218.03 Expiration Date May 26, 2021

By *Manuel Perez* Miami Dade Product Control

ANTHONY LYNN MILLER LICENSE No. 58705

Professional Engineer STATE OF FLORIDA

A. LYNN MILLER, P.E. FL P.E.# 58705


TABLE 7A

1 x 4 x .375 Alum. Tube & "T" Mullion		Mullion Capacity Table (lbs/ft ²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading	
Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)		Mullion Capacity (lbs/ft2)		Anchor Capacity Required (lbs)			
Mull Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	506	170.0	992	170.0	519	170.0	1116	170.0	521	170.0	1240	170.0	521	170.0	1488	170.0	521	170.0	1735	170.0	521	170.0	1983	170.0	521
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	661	170.0	1275	170.0	677	170.0	1417	170.0	680	170.0	1700	170.0	680	170.0	1983	170.0	680	170.0	2024	170.0	680
	50.625 in	170.0	747	170.0	563	170.0	896	170.0	631	170.0	1046	170.0	684	170.0	1195	170.0	723	170.0	1345	170.0	747	170.0	1494	170.0	756	170.0	1793	170.0	756	156.0	1919	170.0	756	136.5	1919	170.0	766
	54 in	170.0	797	170.0	612	170.0	956	170.0	691	170.0	1116	170.0	754	170.0	1275	170.0	803	170.0	1434	170.0	837	170.0	1594	170.0	856	159.9	1799	170.0	861	137.1	1799	170.0	861	120.0	1799	170.0	881
	60 in	170.0	885	170.0	701	170.0	1063	170.0	797	170.0	1240	170.0	878	170.0	1417	170.0	944	170.0	1594	170.0	996	155.5	1619	170.0	1033	129.6	1619	170.0	1063	111.0	1619	170.0	1063	97.2	1619	170.0	1063
	63 in	170.0	930	170.0	745	170.0	1116	170.0	850	170.0	1302	170.0	940	170.0	1468	170.0	1015	158.7	1542	170.0	1076	141.0	1542	170.0	1122	117.5	1542	168.5	1158	100.7	1542	167.9	1157	88.1	1542	167.9	1157
	66 in	170.0	974	170.0	789	170.0	1169	170.0	903	170.0	1364	170.0	1002	160.6	1472	170.0	1086	142.8	1472	168.8	1148	128.5	1472	158.8	1130	107.1	1472	147.8	1108	91.8	1472	146.0	1104	80.3	1472	146.0	1104
	72 in	170.0	1063	170.0	878	170.0	1275	170.0	1009	150.8	1320	166.2	1101	132.0	1320	149.9	1082	117.3	1320	137.8	1066	105.6	1320	128.6	1049	88.0	1320	117.0	1024	75.4	1320	112.6	1013	68.0	1320	112.5	1012
	76 in	170.0	1122	170.0	937	149.6	1184	159.4	1013	128.2	1184	139.8	994	112.2	1184	125.7	978	99.7	1184	115.3	964	89.8	1184	107.5	952	74.8	1184	97.6	935	64.1	1184	93.1	927	56.1	1164	92.3	925
	78 in	166.1	1124	170.0	967	138.4	1124	147.0	965	118.6	1124	128.8	947	103.8	1124	115.6	931	92.3	1124	105.8	918	83.0	1124	98.5	906	69.2	1124	89.0	890	59.3	1124	84.3	881	51.9	1124	83.2	878
	90 in	108.1	844	111.5	750	90.1	844	94.3	736	77.2	844	82.1	724	67.6	844	73.3	712	60.1	844	66.5	702	54.0	844	61.4	693	45.0	844	54.2	678	38.6	844	50.0	668	33.8	844	47.7	662
	96 in	89.1	742	91.5	663	74.2	742	77.2	652	63.6	742	67.2	641	55.7	742	59.8	631	49.5	742	54.1	622	44.5	742	49.8	614	37.1	742	43.6	600	31.8	742	39.8	590	27.8	742	37.5	584
108 in	62.6	586	63.9	530	52.1	566	53.8	521	44.7	586	46.6	513	39.1	586	41.4	505	34.8	586	37.3	498	31.3	586	34.2	492	26.1	586	29.6	481	22.3	586	26.6	472	19.5	586	24.7	466	
111 in	57.6	555	58.8	503	48.0	555	49.5	495	41.2	555	42.9	487	36.0	555	38.0	480	32.0	555	34.2	473	28.8	555	31.3	467	24.0	555	27.1	457	20.6	555	24.3	448	18.0	555	22.4	442	
120 in	45.6	475	46.4	433	38.0	475	39.0	426	32.6	475	33.7	420	28.5	475	29.8	414	25.3	475	26.8	409	22.8	475	24.5	404	19.0	475	21.1	395	16.3	475	18.7	387	14.3	475	17.2	381	
144 in	26.4	330	26.7	305	22.0	330	22.4	301	18.9	330	19.3	297	16.5	330	17.0	293																					

TABLE 7B

Anchor Capacity Table (lbs)																		
Anchor Clip Patterns		Substrate:	2.7k Concrete				3.5k Conc.	Hollow CMU						Filled CMU		PT Wood		Metal
		Anchor Type:	3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon	3/16" Elco Ultracon		1/4" Elco Ultracon		1/4" SS Elco AggreGator	5/16" Elco Ultracon	1/4" SS Elco AggreGator	#10 Steel Screw (G5)	#12 Steel Screw (G5)	#12 Steel Screw (G5)	
			Edge Distance (in):	1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	2"	3-1/8"	2"	0.48"	0.54"	0.324"
			Embedment (in):	1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	2"	1-3/8"	1-3/8"	varies
				1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	2"	1-3/8"	1-3/8"	varies
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1&2):		390 lbs	390 lbs	450 lbs	890 lbs	1644 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	664 lbs	946 lbs	341 lbs	442 lbs	560 lbs		
4 Anchors @ 2.25" Min. O.C. / Standard (or Offset) Clip (Fig. 3):		700 lbs	700 lbs	580 lbs	1410 lbs	952 lbs	N/A	560 lbs	N/A	630 lbs	N/A	880 lbs	N/A	682 lbs	885 lbs	1120 lbs		
8 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 4):		960 lbs	1400 lbs	N/A	N/A	N/A	N/A	760 lbs	N/A	N/A	N/A	N/A	N/A	1363 lbs	1770 lbs	2240 lbs		
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 5):		780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	748 lbs	880 lbs	1892 lbs	682 lbs	885 lbs	1120 lbs		
6 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 6):		1170 lbs	1170 lbs	1020 lbs	2340 lbs	2844 lbs	810 lbs	840 lbs	N/A	1140 lbs	1122 lbs	1320 lbs	2838 lbs	1022 lbs	1327 lbs	1680 lbs		
4 Anchors @ 0.45" Min. O.C. / U-Clip, into .125" Alum. (Fig. 7):		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	1430 lbs		
2 Anchors @ 2.25" Min. O.C. / F-Clip (Fig. 8):		350 lbs	350 lbs	290 lbs	705 lbs	476 lbs	N/A	280 lbs	N/A	315 lbs	N/A	440 lbs	N/A	341 lbs	442 lbs	560 lbs		
4 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 9):		480 lbs	700 lbs	N/A	N/A	N/A	N/A	380 lbs	N/A	N/A	N/A	N/A	N/A	682 lbs	885 lbs	1120 lbs		

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP.



ANGLE CLIP (FIGURES 5&6) MUST BE USED IN PAIRS.


TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.

ANCHOR CAPACITY ADJUSTMENT FORMULA:

$(DP_{REQ}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP. REQ.}$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED as complying with the Florida Building Code Acceptance No. 16-0218.03 Expiration Date May 26, 2021 By Miami/Dade Product Control

ANTHONY LYNN MILLER LICENSE No. 58705 A. LYNN MILLER, P.E. FL P.E.# 58705

1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
NOKOMIS, FL 34274
FL CERT. OF AUTH.# 29296

IMPACT-RESISTANT ALUMINUM TUBE MULLIONS

1 X 4 X .375 MULL SPECS

6300JR

11 of 25

Sheet

1 of 25

Rev: B

Scale: N/A

Checked By: J ROSOWSKI

Date: 08/29/11

Revised: 10/10/14

NEW MULLS TO SHEETSET

TABLE 8A

1.25" x 3.188" x .265" Alum Tube Mull		Mullion Capacity Table (lbs/ft ²)																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																			
		50 in		60 in		70 in		80 in		90 in		100 in		120 in		140 in		160 in			
		Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading
Mull Length	42 in	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)
	48 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	506	170.0	992	170.0	519	170.0	1116	170.0	521
	50.625 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	681	170.0	1275	170.0	677
	54 in	170.0	747	170.0	563	170.0	898	170.0	631	170.0	1046	170.0	684	170.0	1195	170.0	723	170.0	1345	170.0	747
	58 in	170.0	797	170.0	612	170.0	956	170.0	691	170.0	1116	170.0	754	170.0	1275	170.0	803	170.0	1468	170.0	856
	60 in	170.0	885	170.0	701	170.0	1083	170.0	797	158.9	1158	170.0	878	139.0	1158	167.4	930	123.6	1158	156.8	919
	63 in	170.0	930	170.0	745	180.1	1051	170.0	850	137.2	1051	155.9	862	120.1	1051	142.0	848	106.7	1051	132.3	837
	66 in	167.1	957	170.0	789	139.3	957	151.6	805	119.4	857	134.0	790	104.4	957	121.6	777	92.8	957	112.8	767
	72 in	128.7	804	135.2	698	107.3	804	115.2	684	91.9	804	101.3	671	80.4	804	91.4	680	71.5	804	84.1	650
	76 in	109.4	722	114.4	630	91.2	722	97.2	618	78.2	722	85.3	606	68.4	722	76.7	596	60.8	722	70.3	588
	78 in	101.2	685	105.8	600	84.4	685	89.6	588	72.3	685	78.5	577	63.3	685	70.5	568	56.2	685	64.5	560
	80 in	65.9	515	68.0	457	54.9	515	57.5	449	47.1	515	50.1	441	41.2	515	44.7	434	36.6	515	40.8	428
	96 in	54.3	453	55.8	404	45.3	453	47.1	397	38.8	453	41.0	391	33.9	453	36.4	385	30.2	453	33.0	379
	108 in	38.1	358	39.0	323	31.8	358	32.8	318	27.2	358	28.4	313	23.8	358	25.2	308	21.2	358	22.7	304
	111 in	35.1	338	35.8	306	29.3	338	30.1	301	25.1	338	26.1	297	22.0	338	23.2	293	19.5	338	20.9	289
	120 in	27.8	290	28.3	264	23.2	290	23.8	260	19.9	290	20.6	256	17.4	290	18.2	253	15.4	290	16.4	249
	144 in	16.1	201	16.3	186																

TABLE 8B

Anchor Clip Patterns		Anchor Capacity Table (lbs)											
		Substrate:				2.7k Concrete				3.5k Conc.			
		Anchor Type:		3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon		3/16" Elco Ultracon		1/4" Elco Ultracon	
		Edge Distance (in)	Embedment (in)	1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	1"
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1)				390 lbs	390 lbs	450 lbs	690 lbs	1644 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs
4 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 2)				480 lbs	700 lbs	N/A	N/A	N/A	N/A	380 lbs	N/A	N/A	N/A
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3)				780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	880 lbs
4 Anchors @ 0.45" Min. O.C. / U-Clip, Into .125" Alum. (Fig. 4)				N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
1 Anchor / F-Clip (Fig. 5)				195 lbs	195 lbs	225 lbs	445 lbs	822 lbs	135 lbs	140 lbs	177 lbs	370 lbs	187 lbs
2 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 6)				240 lbs	350 lbs	N/A	N/A	N/A	N/A	190 lbs	N/A	N/A	N/A

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP.

FIGURE 1:




FIGURE 2:




FIGURE 3:



FIGURE 4:




FIGURE 5:





FIGURE 6:



ANGLE CLIP MUST BE USED IN PAIRS.


TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.

ANCHOR CAPACITY ADJUSTMENT FORMULA:

$$(DP_{REQ}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP. REQ.}$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED as complying with the Florida Building Code Acceptance No. 16-0218.03 Expiration Date 12/31/2021

By *Manuel Perez*
Miami Dade Product Control


ANTHONY LYNN MILLER
LICENSE
No. 58705
9/8/16
STATE OF FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
FL P.E.# 58705

TABLE 9A

1.25 x 3.25 x .100 Alum. Tube Mullion		Mullion Capacity Table (lbs/ft ²)																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																			
		50 in		60 in		70 in		80 in		90 in		100 in		120 in		140 in		160 in			
		Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading
Mullion Length		Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)
42 in		170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	508	170.0	992	170.0	519	170.0	1118	170.0	521
48 in		170.0	708	170.0	524	170.0	850	170.0	584	167.6	978	170.0	630	146.7	978	170.0	661	130.4	978	170.0	677
50.625 in		170.0	747	170.0	563	170.0	896	170.0	631	150.7	927	170.0	684	131.9	927	166.5	708	117.2	927	159.1	699
54 in		170.0	797	170.0	612	154.5	869	170.0	691	132.5	869	153.9	683	115.9	869	141.8	689	103.0	869	134.0	660
60 in		143.2	746	153.8	634	118.4	746	132.3	620	102.3	746	117.6	608	89.5	746	107.8	599	79.6	746	101.0	592
63 in		123.7	677	132.0	579	103.1	677	113.2	566	88.4	677	100.4	555	77.3	677	91.4	546	68.7	677	85.2	539
66 in		107.8	617	114.1	530	89.7	617	97.6	519	78.9	617	86.3	509	67.3	617	78.3	500	59.8	617	72.6	494
72 in		82.9	518	87.1	450	69.1	518	74.2	440	59.2	518	65.2	432	51.8	518	58.8	425	48.1	518	54.2	419
76 in		70.5	465	73.7	406	58.7	465	62.6	398	50.3	465	54.9	390	44.1	465	49.4	384	39.2	465	45.3	378
78 in		65.2	441	68.0	387	54.3	441	57.7	379	46.6	441	50.6	372	40.8	441	45.4	368	36.2	441	41.6	380
90 in		42.4	332	43.8	295	35.4	332	37.0	289	30.3	332	32.3	284	28.5	332	28.8	280	23.6	332	26.1	276
96 in		35.0	291	35.9	260	29.1	291	30.3	256	25.0	291	26.4	252	21.9	291	23.5	248	19.4	291	21.3	244
108 in		24.6	230	25.1	208	20.5	230	21.1	205	17.5	230	18.3	201	15.4	230	16.2	198				
111 in		22.6	218	23.1	197	18.9	218	19.4	194	16.2	218	16.8	191	14.1	218	14.9	188				
120 in		17.9	187	18.2	170	14.9	187	15.3	167												

TABLE 9B

Anchor Clip Patterns		Anchor Capacity Table (lbs)											
		Substrate:				2.7k Concrete				3.5k Conc.			
		Anchor Type:		3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon		3/16" Elco Ultracon		1/4" Elco Ultracon	
		Edge Distance (in):	Embedment (in):	1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	1"
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1):				390 lbs	390 lbs	450 lbs	890 lbs	1844 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs
4 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 2):				480 lbs	700 lbs	N/A	N/A	N/A	N/A	380 lbs	N/A	N/A	N/A
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3):				780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	880 lbs
3 Anchors @ 0.54" Min. O.C. / U-Clip, into .100" Alum. (Fig. 4):				N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
1 Anchor / F-Clip (Fig. 5):				195 lbs	195 lbs	225 lbs	445 lbs	822 lbs	135 lbs	140 lbs	177 lbs	370 lbs	332 lbs
2 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 6):				240 lbs	350 lbs	N/A	N/A	N/A	N/A	190 lbs	N/A	N/A	N/A



ANGLE
CLIP MUST
BE USED
IN PAIRS.


TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .100" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.

ANCHOR CAPACITY ADJUSTMENT FORMULA:

$(DP_{REQ}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP. REQ.}$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 16-0218.03
Expiration Date May 26, 2021

By *Manuel Torres*
Miami Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
9/8/16
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
FL P.E.# 58705

TABLE 10A

1.25 x 3.25 x .624 Alum. Tube Mullion		Mullion Capacity Table (lbs/ft²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading	
Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft²)	Anchor Capacity Required (lbs)		
Mullion Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	506	170.0	992	170.0	519	170.0	1116	170.0	521	170.0	1240	170.0	521	170.0	1488	170.0	521	170.0	1735	170.0	521	170.0	1983	170.0	521
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	661	170.0	1275	170.0	677	170.0	1417	170.0	680	170.0	1700	170.0	680	169.7	1979	170.0	680	148.5	1979	170.0	680
	50.625 in	170.0	747	170.0	563	170.0	896	170.0	631	170.0	1046	170.0	684	170.0	1195	170.0	723	170.0	1345	170.0	747	170.0	1494	170.0	756	170.0	1793	170.0	756	152.5	1877	170.0	756	133.5	1877	170.0	756
	54 in	170.0	797	170.0	612	170.0	956	170.0	691	170.0	1116	170.0	754	170.0	1275	170.0	803	170.0	1434	170.0	837	170.0	1594	170.0	856	156.4	1769	170.0	861	134.1	1759	170.0	861	117.3	1759	170.0	861
	60 in	170.0	885	170.0	701	170.0	1063	170.0	797	170.0	1240	170.0	878	170.0	1417	170.0	944	161.1	1511	170.0	996	145.0	1511	170.0	1033	120.8	1511	170.0	1063	103.6	1511	170.0	1063	90.6	1511	170.0	1063
	63 in	170.0	930	170.0	745	170.0	1116	170.0	850	170.0	1302	170.0	940	156.6	1370	170.0	1015	139.2	1370	170.0	1076	125.3	1370	164.0	1082	104.4	1370	155.9	1072	89.5	1370	155.3	1070	78.3	1370	155.3	1070
	66 in	170.0	974	170.0	789	170.0	1169	170.0	903	155.6	1248	170.0	1002	136.2	1248	158.6	1013	121.1	1248	147.1	1000	108.9	1248	139.0	989	90.8	1248	130.4	978	77.8	1248	129.0	975	68.1	1248	129.0	975
	72 in	167.8	1049	170.0	878	139.9	1049	150.2	892	119.9	1049	132.1	875	104.9	1049	119.1	860	93.2	1049	109.7	848	83.9	1049	102.7	838	69.9	1049	94.3	825	59.9	1049	91.2	820	52.4	1049	91.1	820
	76 in	142.7	941	149.1	822	118.9	941	126.8	805	101.9	941	111.2	791	89.2	941	100.0	777	79.3	941	91.7	766	71.4	941	85.5	757	59.5	941	77.6	744	51.0	941	74.0	737	44.6	941	73.3	736
	78 in	132.0	894	137.6	783	110.0	894	116.9	767	94.3	894	102.4	753	82.5	894	91.9	740	73.3	894	84.1	730	66.0	894	78.3	721	55.0	894	70.7	707	47.1	894	67.0	701	41.3	894	66.1	698
	90 in	85.9	671	88.7	596	71.6	671	74.9	585	61.4	671	65.3	575	53.7	671	58.2	566	47.7	671	52.9	558	43.0	671	48.8	551	35.8	671	43.1	539	30.7	671	39.7	531	26.9	671	37.9	526
	96 in	70.8	590	72.8	527	59.0	590	61.4	518	50.6	590	53.4	509	44.3	590	47.5	502	39.3	590	43.0	494	35.4	590	39.6	488	29.5	590	34.7	477	25.3	590	31.6	469	22.1	590	29.8	464
	108 in	49.7	466	50.8	421	41.4	466	42.8	414	35.5	466	37.1	408	31.1	466	32.9	402	27.6	466	29.7	396	24.9	466	27.1	391	20.7	466	23.5	382	17.8	466	21.2	375	15.5	466	19.6	370
	111 in	45.8	441	46.7	400	38.2	441	39.3	393	32.7	441	34.1	387	28.6	441	30.2	382	25.4	441	27.2	376	22.9	441	24.9	372	19.1	441	21.5	363	16.4	441	19.3	356	14.3	441	17.8	351
120 in	36.3	378	36.9	344	30.2	378	31.0	339	25.9	378	26.8	334	22.7	378	23.7	329	20.1	378	21.3	325	18.1	378	19.5	321	15.1	378	16.7	314									
144 in	21.0	262	21.2	242	17.5	262	17.8	239	15.0	262	15.3	236																									

TABLE 10B

Anchor Clip Patterns		Anchor Capacity Table (lbs)											
		Substrate:		2.7k Concrete				3.5k Conc.		Hollow CMU			
		Anchor Type:		3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon		3/16" Elco Ultracon		1/4" Elco Ultracon	
		Edge Distance (in)	Embedment (in)	1"	2-1/2"	1"	2-1/2"	3-1/8"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1):				390 lbs	390 lbs	450 lbs	690 lbs	1644 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs
4 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 2):				480 lbs	700 lbs	N/A	N/A	N/A	N/A	380 lbs	N/A	N/A	N/A
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3):				780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	748 lbs
3 Anchors @ 0.54" Min. O.C. / U-Clip, into .100" Alum. (Fig. 4):				N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
1 Anchor / F-Clip (Fig. 5):				195 lbs	195 lbs	225 lbs	445 lbs	822 lbs	135 lbs	140 lbs	177 lbs	370 lbs	187 lbs
2 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 6):				240 lbs	350 lbs	N/A	N/A	N/A	N/A	190 lbs	N/A	N/A	N/A

FIGURE 1:



FIGURE 2:




FIGURE 3:




FIGURE 4:



FIGURE 5:




FIGURE 6:



ANGLE
CLIP MUST
BE USED
IN PAIRS.


TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .100" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.

ANCHOR CAPACITY ADJUSTMENT FORMULA:

$$(DP_{REQ}) \times \left(\frac{ANCHOR CAP. FROM TABLE}{MULLION CAP. FROM TABLE} \right) = ANCHOR CAP. REQ.$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 16-0218.63
Expiration Date May 26, 2021
By *Manuel Perez*
Miami Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
9/8/16
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
FL P.E.# 58705

Title: IMPACT-RESISTANT ALUMINUM TUBE MULLIONS

Description: 1.25 X 3.25 X .624 MULL SPECS

Series: N/A

Scale: N/A

Drawing No: 6300JR

Checked By: J ROSOWSKI

Date: 08/29/11

Revision: 10/10/14

Rev. By: J ROSOWSKI

Date: 10/10/14

NEW MULLS TO SHEETSET

Sheet: 14 of 25

Rev: B

FL CERT. OF AUTH.# 29296

TABLE 11A

TABLE 11A																																									
Mullion Capacity Table (lbs/ft ²)																																									
Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																									
1.25 x 3.94 x .624 Alum. Tube Mullion		50 in								60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading					
		Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)						
Mullion Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	506	170.0	992	170.0	519	170.0	1116	170.0	521	170.0	1240	170.0	521	170.0	1488	170.0	521	170.0	1735	170.0	521	170.0	1983	170.0	521				
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	661	170.0	1275	170.0	677	170.0	1417	170.0	680	170.0	1700	170.0	680	170.0	1983	170.0	680	170.0	2267	170.0	680				
	50.625 in	170.0	747	170.0	563	170.0	896	170.0	631	170.0	1046	170.0	684	170.0	1195	170.0	723	170.0	1345	170.0	747	170.0	1494	170.0	756	170.0	1793	170.0	756	170.0	2092	170.0	756	170.0	2391	170.0	756				
	54 in	170.0	797	170.0	612	170.0	956	170.0	691	170.0	1116	170.0	754	170.0	1275	170.0	803	170.0	1434	170.0	837	170.0	1594	170.0	856	170.0	1913	170.0	861	170.0	2231	170.0	861	160.2	2403	170.0	861				
	60 in	170.0	885	170.0	701	170.0	1063	170.0	797	170.0	1240	170.0	878	170.0	1417	170.0	944	170.0	1594	170.0	996	170.0	1771	170.0	1033	170.0	2125	170.0	1063	148.3	2163	170.0	1063	129.8	2163	170.0	1063				
	63 in	170.0	930	170.0	745	170.0	1116	170.0	850	170.0	1302	170.0	940	170.0	1488	170.0	1015	170.0	1673	170.0	1076	170.0	1859	170.0	1122	155.9	2060	170.0	1169	134.5	2060	170.0	1171	117.7	2060	170.0	1171				
	66 in	170.0	974	170.0	789	170.0	1169	170.0	903	170.0	1364	170.0	1002	170.0	1558	170.0	1086	170.0	1753	170.0	1155	170.0	1948	170.0	1210	143.0	1966	170.0	1275	122.6	1966	170.0	1286	107.2	1966	170.0	1286				
	72 in	170.0	1063	170.0	878	170.0	1275	170.0	1009	170.0	1488	170.0	1126	170.0	1700	170.0	1228	154.1	1734	170.0	1315	138.7	1734	169.8	1386	115.6	1734	155.9	1364	99.1	1734	150.4	1352	86.7	1734	150.2	1352				
	76 in	170.0	1122	170.0	937	170.0	1346	170.0	1080	168.5	1556	170.0	1209	147.4	1556	165.2	1285	131.1	1556	151.5	1266	117.9	1556	141.3	1251	98.3	1556	128.3	1229	84.2	1556	122.3	1219	73.7	1556	121.2	1216				
	78 in	170.0	1151	170.0	967	170.0	1381	170.0	1116	155.9	1477	169.3	1245	136.4	1477	152.0	1224	121.2	1477	139.1	1206	109.1	1477	129.5	1191	90.9	1477	116.9	1169	77.9	1477	110.8	1158	68.2	1477	109.3	1154				
	90 in	142.0	1110	146.5	986	118.4	1110	123.9	968	101.5	1110	107.9	951	88.8	1110	96.3	936	78.9	1110	87.5	922	71.0	1110	80.7	910	59.2	1110	71.3	891	50.7	1110	65.6	878	44.4	1110	62.7	870				
	96 in	117.0	975	120.3	872	97.5	975	101.5	856	83.6	975	88.3	842	73.2	975	78.5	829	65.0	975	71.2	817	58.5	975	65.4	807	48.8	975	57.4	789	41.8	975	52.3	776	36.6	975	49.3	767				
	108 in	82.2	771	84.0	696	68.5	771	70.7	685	58.7	771	61.3	674	51.4	771	54.3	654	45.7	771	49.0	655	41.1	771	44.9	647	34.3	771	38.9	632	29.4	771	35.0	621	25.7	771	32.4	612				
	111 in	75.7	730	77.3	661	63.1	730	65.0	650	54.1	730	56.3	640	47.3	730	49.9	631	42.1	730	45.0	622	37.9	730	41.1	614	31.5	730	35.6	600	27.0	730	31.9	589	23.7	730	29.5	581				
120 in	59.9	624	61.0	569	49.9	624	51.2	560	42.8	624	44.3	552	37.5	624	39.2	544	33.3	624	35.3	537	30.0	624	32.2	531	25.0	624	27.7	519	21.4	624	24.6	509	18.7	624	22.5	501					
144 in	34.7	433	35.1	400	28.9	433	29.4	395	24.8	433	25.4	390	21.7	433	22.4	385	19.3	433	20.0	381	17.3	433	18.2	376																	

TABLE 11B

Anchor Clip Patterns		Anchor Capacity Table (lbs)																			
		Substrate:		2.7k Concrete				3.5k Conc.	Hollow CMU						Filled CMU	PT Wood		Metal			
		Anchor Type:		3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon	3/16" Elco Ultracon		1/4" Elco Ultracon		1/4" SS Elco AggreGator	5/16" Elco Ultracon	1/4" SS Elco AggreGator	#10 Steel Screw (G5)	#12 Steel Screw (G5)	#12 Steel Screw (G5)			
		Edge Distance (in):		1"		2-1/2"		3-1/8"	1"		2-1/2"		1"	2-1/2"		2"	3-1/8"	2"	0.48"	0.54"	0.324"
		Embedment (in):		1-3/4"		1-3/4"		1-3/4"	1-3/4"	2"	1-1/4"		1-1/4"		1-1/4"	1-1/4"	1-1/4"	1-1/4"	2"	1-3/8"	1-3/8"
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1)		390 lbs	390 lbs	450 lbs	890 lbs	1644 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	664 lbs	946 lbs	341 lbs	442 lbs	560 lbs					
4 Anchors @ 1.15" Min. O.C. / Standard (or Offset) Clip (Fig. 2)		480 lbs	700 lbs	N/A	N/A	N/A	N/A	380 lbs	N/A	N/A	N/A	N/A	N/A	682 lbs	885 lbs	1120 lbs					
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3)		780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	N/A	N/A	N/A	N/A	N/A	N/A	1267 lbs					
4 Anchors @ 0.54" Min. O.C. / U-Clip, Into .100" Alum. (Fig. 4)		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A					
1 Anchor / F-Clip (Fig. 5)		195 lbs	195 lbs	225 lbs	445 lbs	822 lbs	135 lbs	140 lbs	177 lbs	370 lbs	187 lbs	332 lbs	473 lbs	170 lbs	221 lbs	280 lbs					
2 Anchors @ 1.15" Min. O.C. / F-Clip (Fig. 6)		240 lbs	350 lbs	N/A	N/A	N/A	N/A	190 lbs	N/A	N/A	N/A	N/A	N/A	N/A	341 lbs	442 lbs	560 lbs				

FIGURE 1:




FIGURE 2:




FIGURE 3:




FIGURE 4:



FIGURE 5:





FIGURE 6:



ANGLE
CLIP MUST
BE USED
IN PAIRS.


TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .100" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.


ANCHOR CAPACITY ADJUSTMENT FORMULA:

$$(DP_{REQ}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP. REQ.}$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



1.25" X 3.94" X .624"
MULLION



IMPACT-RESISTANT ALUMINUM TUBE MULLIONS

1.25 X 3.94 X .624 MULL SPECS

Sheet: 15 of 25

Scale: N/A

Drawing No: 6300JR

Checked By: J ROSOWSKI

Date: 08/29/11

Revision: 10/10/14 NEW MULLS TO SHEETSET

Rev. By: J ROSOWSKI

Date: 10/10/14

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 16-0218-03
Expiration Date 12/31/2021

By: *Manuel Perez*
Miami Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
a-z 8/16
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
FL P.E.# 58705

TABLE 12A

2 x 4 x .25 Alum. Tube Mullion		Mullion Capacity Table (lbs/ft ²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading					
Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft2)	Anchor Capacity Required (lbs)				
Mull Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	506	170.0	992	170.0	630	170.0	1133	170.0	661	170.0	1275	170.0	677	170.0	1417	170.0	680	170.0	1700	170.0	680	170.0	1983	170.0	680
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	661	170.0	1275	170.0	677	170.0	1417	170.0	680	170.0	1700	170.0	680	170.0	1983	170.0	680	170.0	2287	170.0	680
	50.625 in	170.0	747	170.0	583	170.0	896	170.0	631	170.0	1046	170.0	684	170.0	1195	170.0	723	170.0	1345	170.0	747	170.0	1494	170.0	756	170.0	1793	170.0	756	170.0	2092	170.0	756	170.0	2391	170.0	756
	54 in	170.0	797	170.0	612	170.0	956	170.0	691	170.0	1116	170.0	754	170.0	1275	170.0	803	170.0	1434	170.0	837	170.0	1594	170.0	856	170.0	1913	170.0	861	170.0	2231	170.0	861	170.0	2550	170.0	861
	60 in	170.0	885	170.0	701	170.0	1063	170.0	797	170.0	1240	170.0	878	170.0	1417	170.0	944	170.0	1584	170.0	996	170.0	1771	170.0	1033	170.0	2125	170.0	1063	170.0	2479	170.0	1063	160.8	2680	170.0	1083
	63 in	170.0	930	170.0	745	170.0	1116	170.0	850	170.0	1302	170.0	940	170.0	1488	170.0	1015	170.0	1673	170.0	1076	170.0	1859	170.0	1122	170.0	2231	170.0	1169	166.7	2553	170.0	1171	145.9	2553	170.0	1171
	66 in	170.0	974	170.0	789	170.0	1169	170.0	903	170.0	1364	170.0	1002	170.0	1558	170.0	1086	170.0	1753	170.0	1155	170.0	1948	170.0	1210	170.0	2338	170.0	1275	151.9	2437	170.0	1286	132.9	2437	170.0	1286
	72 in	170.0	1063	170.0	878	170.0	1275	170.0	1009	170.0	1488	170.0	1126	170.0	1700	170.0	1228	170.0	1913	170.0	1315	170.0	2125	170.0	1387	145.6	2184	170.0	1488	124.8	2184	170.0	1529	109.2	2184	170.0	1530
	76 in	170.0	1122	170.0	937	170.0	1346	170.0	1080	170.0	1570	170.0	1209	170.0	1794	170.0	1322	165.1	1960	170.0	1421	148.8	1960	170.0	1505	123.8	1960	161.6	1548	106.1	1960	154.0	1535	92.9	1960	152.7	1531
	78 in	170.0	1151	170.0	967	170.0	1381	170.0	1116	170.0	1611	170.0	1250	170.0	1842	170.0	1369	152.7	1861	170.0	1474	137.4	1861	163.1	1500	114.5	1861	147.3	1473	98.2	1861	139.6	1459	85.9	1861	137.6	1454
	90 in	170.0	1328	170.0	1144	149.1	1398	156.0	1219	127.8	1398	136.0	1198	111.8	1398	121.3	1179	99.4	1398	110.2	1162	89.5	1398	101.6	1147	74.5	1398	89.8	1122	63.9	1398	82.7	1105	55.9	1398	78.9	1096
	96 in	147.4	1229	151.5	1098	122.9	1229	127.8	1079	105.3	1229	111.2	1061	92.1	1229	98.9	1044	81.9	1229	89.6	1029	73.7	1229	82.4	1016	61.4	1229	72.2	993	52.7	1229	65.9	977	46.1	1229	62.1	967
	108 in	103.5	971	105.8	877	86.3	971	89.0	862	74.0	971	77.2	849	64.7	971	68.4	837	57.5	971	61.8	825	51.8	971	56.5	815	43.1	971	49.0	796	37.0	971	44.0	782	32.4	971	40.8	771
	111 in	95.4	919	97.3	832	79.5	919	81.9	819	68.1	919	70.9	806	59.6	919	62.9	794	53.0	919	56.7	784	47.7	919	51.8	774	39.7	919	44.8	756	34.1	919	40.2	742	29.8	919	37.1	732
120 in	75.5	786	76.8	716	62.9	786	64.5	705	53.9	786	55.8	695	47.2	786	49.4	686	41.9	786	44.4	677	37.7	786	40.5	668	31.5	786	34.9	653	27.0	786	31.0	641	23.6	786	28.4	631	
144 in	43.7	546	44.2	504	36.4	546	37.0	498	31.2	546	31.9	491	27.3	546	28.2	485	24.3	546	25.3	479	21.8	546	22.9	474	18.2	546	19.5	464	15.6	546	17.2	455	13.7	546	15.5	448	

TABLE 12B

Anchor Capacity Table (lbs)																	
Anchor Clip Patterns	Substrate:	2.7k Concrete				3.5k Conc.	Hollow CMU						Filled CMU		PT Wood		Metal
	Anchor Type:	3/16" Eico Ultracon		1/4" Eico Ultracon		5/16" Eico Ultracon	3/16" Eico Ultracon		1/4" Eico Ultracon		1/4" SS Eico AggreGator	5/16" Eico Ultracon	1/4" SS Eico AggreGator	#10 Steel Screw (G5)	#12 Steel Screw (G5)	#12 Steel Screw (G5)	
		Edge Distance (in)	1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	2"	3-1/8"	2"	0.48"	0.54"	0.324"
		Embedment (in)	1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	2"	1-3/8"	1-3/8"	varies
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 18.2)		390 lbs	390 lbs	450 lbs	890 lbs	1644 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	664 lbs	946 lbs	341 lbs	442 lbs	560 lbs	
4 Anchors @ 2.68" Min. O.C. / Standard (or Offset) Clip (Fig. 3)		740 lbs	740 lbs	630 lbs	1485 lbs	1424 lbs	N/A	560 lbs	N/A	695 lbs	N/A	880 lbs	N/A	682 lbs	885 lbs	1120 lbs	
6 Anchors @ 1.71" Min. O.C. / Standard (or Offset) Clip (Fig. 4)		885 lbs	1050 lbs	758 lbs	1946 lbs	N/A	N/A	705 lbs	N/A	799 lbs	N/A	N/A	N/A	1022 lbs	1327 lbs	1680 lbs	
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 5)		780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	748 lbs	880 lbs	1892 lbs	682 lbs	885 lbs	1120 lbs	
6 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 6)		1170 lbs	1170 lbs	1020 lbs	2340 lbs	2844 lbs	810 lbs	840 lbs	N/A	1140 lbs	1122 lbs	1320 lbs	2838 lbs	1022 lbs	1327 lbs	1680 lbs	
3 Anchors @ 1.34" Min. O.C. / U-Clip, Into .125" Alum. (Fig. 7)		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	2148 lbs	
6 Anchors @ 0.64" Min. O.C. / U-Clip, Into .125" Alum. (Fig. 8)		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
2 Anchors @ 2.68" Min. O.C. / F-Clip (Fig. 9)		370 lbs	370 lbs	315 lbs	743 lbs	712 lbs	N/A	280 lbs	N/A	348 lbs	N/A	440 lbs	N/A	341 lbs	442 lbs	560 lbs	
3 Anchors @ 1.71" Min. O.C. / F-Clip (Fig. 10)		443 lbs	525 lbs	379 lbs	973 lbs	N/A	N/A	353 lbs	N/A	399 lbs	N/A	N/A	N/A	511 lbs	664 lbs	840 lbs	

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP.

CIRCLED VALUES ARE USED IN THE EXAMPLE ON SHEET 24.





TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.

ANCHOR CAPACITY ADJUSTMENT FORMULA:

$$(DP_{REQ}) \times \left(\frac{ANCHOR CAP.^{* FROM TABLE}}{MULLION CAP.^{* FROM TABLE}} \right) = ANCHOR CAP.^{* REQ.}$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 16-0218.03
Expiration Date MAY 26, 2021
By Manuel Perez
Miami Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
A. Lynn Miller
4/18/16
STATE OF FLORIDA
PROFESSIONAL ENGINEER

A. LYNN MILLER, P.E.
FL P.E.# 58705


TABLE 13A

Mullion Capacity Table (lbs/ft ²)																																					
2 x 6 x .25 Alum. Tube Mullion		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading					
		Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)						
Mull Length	42 in	170.0	820	170.0	435	170.0	744	170.0	478	170.0	888	170.0	508	170.0	992	170.0	519	170.0	1118	170.0	521	170.0	1240	170.0	521	170.0	1488	170.0	521	170.0	1735	170.0	521	170.0	1983	170.0	521
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	661	170.0	1275	170.0	677	170.0	1417	170.0	680	170.0	1700	170.0	680	170.0	1883	170.0	680	170.0	2267	170.0	680
	50.625 in	170.0	747	170.0	583	170.0	898	170.0	631	170.0	1048	170.0	684	170.0	1195	170.0	723	170.0	1345	170.0	747	170.0	1484	170.0	758	170.0	1783	170.0	758	170.0	2092	170.0	758	170.0	2391	170.0	758
	54 in	170.0	797	170.0	612	170.0	958	170.0	691	170.0	1118	170.0	754	170.0	1275	170.0	803	170.0	1434	170.0	837	170.0	1584	170.0	858	170.0	1913	170.0	861	170.0	2231	170.0	861	170.0	2550	170.0	861
	60 in	170.0	885	170.0	701	170.0	1063	170.0	797	170.0	1240	170.0	878	170.0	1417	170.0	944	170.0	1584	170.0	996	170.0	1771	170.0	1033	170.0	2125	170.0	1063	170.0	2479	170.0	1063	170.0	2833	170.0	1063
	63 in	170.0	930	170.0	745	170.0	1116	170.0	850	170.0	1302	170.0	940	170.0	1488	170.0	1015	170.0	1673	170.0	1076	170.0	1859	170.0	1122	170.0	2231	170.0	1189	170.0	2803	170.0	1171	170.0	2975	170.0	1171
	66 in	170.0	974	170.0	789	170.0	1169	170.0	903	170.0	1384	170.0	1002	170.0	1558	170.0	1088	170.0	1753	170.0	1155	170.0	1948	170.0	1210	170.0	2338	170.0	1275	170.0	2727	170.0	1288	170.0	3117	170.0	1288
	72 in	170.0	1063	170.0	878	170.0	1275	170.0	1009	170.0	1468	170.0	1126	170.0	1700	170.0	1228	170.0	1913	170.0	1315	170.0	2125	170.0	1387	170.0	2550	170.0	1488	170.0	2975	170.0	1529	170.0	3400	170.0	1530
	76 in	170.0	1122	170.0	937	170.0	1346	170.0	1080	170.0	1570	170.0	1209	170.0	1794	170.0	1322	170.0	2019	170.0	1421	170.0	2243	170.0	1505	170.0	2692	170.0	1629	170.0	3140	170.0	1694	170.0	3589	170.0	1705
	78 in	170.0	1151	170.0	967	170.0	1381	170.0	1116	170.0	1611	170.0	1250	170.0	1842	170.0	1389	170.0	2072	170.0	1474	170.0	2302	170.0	1584	170.0	2783	170.0	1700	170.0	3223	170.0	1777	170.0	3883	170.0	1796
	90 in	170.0	1328	170.0	1144	170.0	1594	170.0	1328	170.0	1859	170.0	1498	170.0	2125	170.0	1653	170.0	2391	170.0	1793	170.0	2858	170.0	1918	170.0	3188	170.0	2125	158.0	3413	170.0	2273	136.5	3413	170.0	2381
	96 in	170.0	1417	170.0	1232	170.0	1700	170.0	1434	170.0	1983	170.0	1622	170.0	2267	170.0	1784	170.0	2550	170.0	1952	170.0	2833	170.0	2095	160.0	3199	170.0	2338	137.1	3199	166.6	2470	120.0	3199	156.1	2428
108 in	170.0	1584	170.0	1409	170.0	1913	170.0	1647	170.0	2231	170.0	1870	170.0	2550	170.0	2076	164.8	2781	170.0	2271	148.3	2781	161.9	2333	123.6	2781	140.4	2281	105.9	2781	125.9	2234	92.7	2781	116.0	2190	
111 in	170.0	1638	170.0	1454	170.0	1968	170.0	1700	170.0	2293	170.0	1932	170.0	2621	170.0	2149	151.8	2832	162.3	2245	136.8	2832	148.4	2216	113.8	2832	128.4	2166	97.6	2832	115.1	2126	85.4	2632	106.3	2066	
120 in	170.0	1771	170.0	1586	170.0	2125	170.0	1859	154.4	2252	159.9	1991	135.1	2252	141.4	1964	120.1	2252	127.2	1938	106.1	2252	116.1	1915	90.1	2252	99.8	1872	77.2	2252	88.9	1836	67.6	2252	81.4	1808	
144 in	125.1	1564	128.6	1445	104.3	1564	106.1	1425	89.4	1564	91.5	1407	78.2	1564	80.7	1390	69.5	1564	72.3	1373	62.6	1564	65.7	1358	52.1	1564	56.0	1330	44.7	1564	49.2	1305	39.1	1564	44.4	1283	

TABLE 13B

TABLE 13B																
Anchor Capacity Table (lbs)																
Anchor Clip Patterns	Substrate:	2.7k Concrete				3.5k Conc.	Hollow CMU						Filled CMU	PT Wood		Metal
	Anchor Type:	3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon	3/16" Elco Ultracon		1/4" Elco Ultracon		1/4" SS Elco AggreGator	5/16" Elco Ultracon	1/4" SS Elco AggreGator	#10 Steel Screw (G5)	#12 Steel Screw (G5)	#12 Steel Screw (G5)
	Edge Distance (in):	1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	2"	3-1/8"	2"	0.48"	0.54"	0.324"
	Embedment (in):	1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	2"	1-3/8"	1-3/8"	varies
2 Anchors @ 4.75" Min. O.C. / Standard or Offset Clip (Fig. 1&2):		390 lbs	390 lbs	450 lbs	890 lbs	1644 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	684 lbs	946 lbs	341 lbs	442 lbs	560 lbs
4 Anchors @ 4.68" Min. O.C. / Standard (or Offset) Clip (Fig. 3):		780 lbs	780 lbs	900 lbs	1780 lbs	3232 lbs	540 lbs	560 lbs	708 lbs	1480 lbs	748 lbs	1272 lbs	1892 lbs	682 lbs	885 lbs	1120 lbs
8 Anchors @ 1.71" Min. O.C. / Standard (or Offset) Clip (Fig. 4):		1180 lbs	1400 lbs	1010 lbs	2595 lbs	N/A	N/A	940 lbs	N/A	1065 lbs	N/A	N/A	N/A	1363 lbs	1770 lbs	2240 lbs
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips (Fig. 5):		780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	748 lbs	880 lbs	1892 lbs	682 lbs	685 lbs	1120 lbs
8 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 6):		1560 lbs	1560 lbs	1360 lbs	3120 lbs	3792 lbs	1080 lbs	1120 lbs	N/A	1520 lbs	1496 lbs	1760 lbs	3784 lbs	1363 lbs	1770 lbs	2240 lbs
12 Anchors @ 1.5" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 7):		1660 lbs	2100 lbs	1440 lbs	3780 lbs	N/A	N/A	1320 lbs	N/A	1500 lbs	N/A	N/A	N/A	N/A	N/A	1430 lbs
4 Anchors @ 1.34" Min. O.C. / U-Clip, Into .125" Alum. (Fig. 8):		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	2861 lbs
8 Anchors @ 0.64" Min. O.C. / U-Clip, Into .125" Alum. (Fig. 9):		N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	
2 Anchors @ 4.68" Min. O.C. / F-Clip (Fig. 10):		390 lbs	390 lbs	450 lbs	890 lbs	1616 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	636 lbs	946 lbs	341 lbs	442 lbs	560 lbs
4 Anchors @ 1.71" Min. O.C. / F-Clip (Fig. 11):		590 lbs	700 lbs	505 lbs	1298 lbs	N/A	N/A	470 lbs	N/A	533 lbs	N/A	N/A	N/A	682 lbs	885 lbs	1120 lbs

NOTE: FOR THE OFFSET CLIP, USE THE SAME ANCHOR PATTERN AND ANCHOR VALUES AS THE STANDARD CLIP.



ANGLE
CLIP
(FIGURES
5 - 7)
MUST BE
USED IN
PAIRS.


TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.


ANCHOR CAPACITY ADJUSTMENT FORMULA:

$$(DP_{REG}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP.}_{REG}$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 16-0218.03
Expiration Date May 26, 2021
By Manuel Perez
Miami/Dade Product Control



RCI®
1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274

Title: **IMPACT-RESISTANT ALUMINUM TUBE MULLIONS**

Description: 2 X 6 X .25 MULL SPECS
--

Series:	N/A	Scale:	N/A	Drawing No.	6300JR	Sheet:	17 of 25
---------	-----	--------	-----	-------------	--------	--------	----------

Drawn By:	IN/A	Date:	08/20/11	Rev:	B
Checked By:		Date:			

J. KRUSOWSKI	Date:	08/29/11	Revision:	NEW MILLIS TO SHEETSET
Rev. By:		10/10/11		

TABLE 14A

1.26" x 2.11" x .125" Alum Tube Mull		Mullion Capacity Table (lbs/ft ²)																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																			
		50 in		60 in		70 in		80 in		90 in		100 in		120 in		140 in		160 in			
		Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading	Rectangular Loading	Trap/Triang. Loading
Mull Length	42 in	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)
	48 in	144.2	526	167.0	428	120.2	526	148.9	419	103.0	526	138.9	414	90.1	526	134.1	411	72.1	526	134.1	411
	50.625 in	96.6	403	108.0	333	80.5	403	94.7	325	69.0	403	88.4	320	60.4	403	81.4	317	53.7	403	79.1	315
	54 in	82.3	362	91.0	301	68.6	362	79.3	294	58.8	362	71.9	289	51.5	362	67.2	286	45.7	362	64.6	284
	60 in	67.8	318	74.1	267	56.5	318	64.2	261	48.5	318	57.7	256	42.4	318	53.5	253	37.7	318	50.8	250
	63 in	49.5	258	53.1	219	41.2	258	45.7	214	35.3	258	40.7	210	30.9	258	37.2	207	27.5	258	34.9	204
	66 in	42.7	234	45.6	200	35.6	234	39.1	195	30.5	234	34.7	192	26.7	234	31.6	189	23.7	234	29.4	186
	72 in	37.2	213	39.4	183	31.0	213	33.7	179	26.5	213	29.6	176	23.2	213	27.0	173	20.6	213	25.1	170
	76 in	28.6	179	30.1	155	23.9	179	25.6	152	20.4	179	22.5	149	17.9	179	20.3	147	15.9	179	18.7	145
	78 in	24.3	161	25.4	140	20.3	161	21.6	137	17.4	161	19.0	135	15.2	161	17.0	133				
	78 in	22.5	152	23.5	133	18.8	152	19.9	131	16.1	152	17.5	128								

TABLE 14B


Anchor Clip Patterns		Anchor Capacity Table (lbs)											
		Substrate:				2.7k Concrete				3.5k Conc.			
		Anchor Type:		3/16" Eiko Ultralon		1/4" Eiko Ultralon		5/16" Eiko Ultralon		3/16" Eiko Ultralon		1/4" Eiko Ultralon	
		Edge Distance (in.)	Embedment (in.)	1"	2-1/2"	1"	2-1/2"	3-1/8"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"
4 Anchors @ 3" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 1)				780 lbs	780 lbs	680 lbs	1560 lbs	1896 lbs	540 lbs	560 lbs	N/A	760 lbs	748 lbs
												880 lbs	1892 lbs
												682 lbs	685 lbs
												1430 lbs	

ANCHOR CAPACITY ADJUSTMENT FORMULA:

$(DP_{REQ}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP. REQ.}$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.


FIGURE 1:



ANGLE CLIP MUST BE USED IN PAIRS.

TABLE NOTES:

- SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.



PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 16-0218.03
Expiration Date 12/31/2021
By *[Signature]*
Miami Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
9-4/8/16
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
FL P.E.# 58705

RG
1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
FL CERT. OF AUTH.# 28296

Title: IMPACT-RESISTANT ALUMINUM TUBE MULLIONS
Description: 1.26 X 2.11 X .125 MULL SPECS
Scale: N/A
Drawing No. 6300JR
Date: 08/29/11
Checked By: J ROSOWSKI
Date: 10/10/14
Revision: NEW MULLS TO SHEETSET
Sheet: 18 of 25
Rev: B

TABLE 15A

3.25" 30 DEG. AL BAY MULL		Mullion Capacity Table (lbs/ft ²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading	
Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)				
Mull Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	506	170.0	992	170.0	519	170.0	1116	170.0	521	170.0	1240	170.0	521	170.0	1488	170.0	521	170.0	1735	170.0	521	170.0	1983	170.0	521
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	661	170.0	1275	170.0	677	170.0	1417	170.0	680	170.0	1522	170.0	680	170.0	1740	170.0	680	170.0	1990	170.0	680
	50.625 in	170.0	747	170.0	563	170.0	896	170.0	631	170.0	1046	170.0	684	170.0	1195	170.0	723	170.0	1345	170.0	747	170.0	1443	170.0	756	170.0	1566	170.0	756	170.0	1760	170.0	756	170.0	2000	170.0	756
	54 in	170.0	797	170.0	612	170.0	956	170.0	691	170.0	1116	170.0	754	170.0	1275	170.0	803	170.0	1433	170.0	837	170.0	1443	170.0	856	170.0	1588	170.0	861	170.0	1770	170.0	861	170.0	2010	170.0	861
	60 in	170.0	885	170.0	701	170.0	1063	170.0	787	170.0	1218	170.0	878	170.0	1481	170.0	944	170.0	1598	170.0	938	170.0	1598	170.0	938	170.0	1693	170.0	938	170.0	1780	170.0	938	170.0	2020	170.0	938
	63 in	170.0	930	170.0	745	170.0	1116	170.0	850	170.0	1218	170.0	914	170.0	1481	170.0	998	170.0	1598	170.0	998	170.0	1693	170.0	998	170.0	1738	170.0	998	170.0	1790	170.0	998	170.0	2030	170.0	998
	66 in	170.0	974	170.0	789	170.0	1169	170.0	893	170.0	1270	170.0	958	170.0	1533	170.0	1047	170.0	1669	170.0	1047	170.0	1669	170.0	1047	170.0	1753	170.0	1047	170.0	1800	170.0	1047	170.0	2040	170.0	1047
	72 in	140.8	880	147.9	784	117.4	880	126.0	748	100.6	880	110.8	734	88.0	880	100.0	722	78.2	880	92.0	712	70.4	880	88.2	703	58.7	880	79.2	693	50.3	880	76.5	688	44.0	880	76.4	688
	76 in	119.7	790	125.1	690	99.8	790	108.4	676	85.5	790	93.3	663	74.8	790	83.9	652	66.5	790	76.9	643	58.9	790	71.7	635	49.9	790	65.1	624	42.8	790	62.1	619	37.4	790	61.5	617
	78 in	110.8	750	115.5	657	92.3	750	98.1	644	79.1	750	85.9	632	69.2	750	77.1	621	61.5	750	70.6	612	55.4	750	65.7	605	46.2	750	59.4	594	39.6	750	56.2	588	34.6	750	55.5	588
	90 in	72.1	563	74.4	500	60.1	563	62.9	491	51.5	563	54.8	483	45.1	563	48.9	475	40.1	563	44.4	468	38.1	563	40.9	462	30.0	563	36.2	452	25.8	563	33.3	445	22.5	563	31.8	442
	96 in	59.4	495	61.1	443	49.5	495	51.5	435	42.4	495	44.8	427	37.1	495	39.9	421	33.0	495	36.1	415	29.7	495	33.2	409	24.8	495	29.1	400	21.2	495	26.8	394	18.6	495	25.0	390
	108 in	41.7	391	42.6	353	34.8	391	35.9	348	29.8	391	31.1	342	26.1	391	27.6	337	23.2	391	24.9	333	20.9	391	22.8	328	17.4	391	19.7	321	14.9	391	17.8	315				
	111 in	38.4	370	39.2	335	32.0	370	33.0	330	27.5	370	28.6	325	24.0	370	25.3	320	21.4	370	22.8	316	19.2	370	20.9	312	16.0	370	18.1	305								
	120 in	30.4	317	30.9	289	25.3	317	26.0	284	21.7	317	22.5	280	19.0	317	19.9	276	16.9	317	17.9	273																
	144 in	17.6	220	17.8	203																																

ANCHOR CAPACITY ADJUSTMENT

TABLE 15B

Anchor Clip Patterns		Anchor Capacity Table (lbs)											
		Substrate:		2.7k Concrete				3.5k Conc.		Hollow CMU			
		Anchor Type:		3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon		3/16" Elco Ultracon		1/4" Elco Ultracon	
		Edge Distance (in):		1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	2"
		Embedment (in):		1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"
2 Anchors @ 5" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 1):				390 lbs	390 lbs	450 lbs	890 lbs	1700 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs
4 Anchors @ 3.5" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 2):				780 lbs	780 lbs	790 lbs	1670 lbs	2525 lbs	540 lbs	560 lbs	N/A	1120 lbs	748 lbs
6 Anchors @ 2.71" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3):				1120 lbs	1120 lbs	958 lbs	2246 lbs	2254 lbs	N/A	840 lbs	N/A	1059 lbs	N/A

FIGURE 1:




FIGURE 2:





FIGURE 3:



ANGLE CLIP (FIGURES 1-3) MUST BE USED IN PAIRS.


TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.

ANCHOR CAPACITY ADJUSTMENT FORMULA:


$(DP_{REQ}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP. REQ.}$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED as complying with the Florida Building Code Acceptance No. 16-0218.03 Expiration Date May 26, 2021 By Manuel Pina Miami Dade Product Control

ANTHONY LYNN MILLER LICENSE No. 58705 4/18/16 STATE OF FLORIDA PROFESSIONAL ENGINEER A. LYNN MILLER, P.E. FL P.E.# 58705



IMPACT-RESISTANT ALUMINUM TUBE MULLIONS 30 DEGREE BAY MULL SPECS 6300JR Drawing No. 19 of 25 Sheet Scale: N/A Date: 08/29/11 Checked By: J ROSOWSKI Date: 10/10/14 Revision: 10/10/14 NEW MULLS TO SHEETSET

TABLE 16A

3.25" 45 DEG. AL BAY MULL		Mullion Capacity Table (lbs/ft ²)																																			
		Opening Width (for vertically-spanning mullions) or Opening Height (for horizontally-spanning mullions)																																			
		50 in				60 in				70 in				80 in				90 in				100 in				120 in				140 in				160 in			
		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading		Rectangular Loading		Trap/Triang. Loading					
Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)	Mullion Capacity (lbs/ft ²)	Anchor Capacity Required (lbs)						
Mull Length	42 in	170.0	620	170.0	435	170.0	744	170.0	478	170.0	868	170.0	506	170.0	992	170.0	519	170.0	1116	170.0	521	170.0	1240	170.0	521	170.0	1488	170.0	521	170.0	1735	170.0	521	170.0	1871	170.0	521
	48 in	170.0	708	170.0	524	170.0	850	170.0	584	170.0	992	170.0	630	170.0	1133	170.0	681	170.0	1275	170.0	677	170.0	1417	170.0	680	170.0	1637	170.0	680	170.0	1837	170.0	680	170.0	1987	170.0	680
	50.625 in	170.0	747	170.0	563	170.0	896	170.0	631	170.0	1046	170.0	684	170.0	1195	170.0	723	170.0	1345	170.0	747	170.0	1494	170.0	756	170.0	1552	170.0	756	170.0	1758	170.0	756	170.0	1918	170.0	756
	54 in	170.0	797	170.0	612	170.0	958	170.0	691	170.0	1116	170.0	754	170.0	1275	170.0	803	170.0	1434	170.0	837	170.0	1552	170.0	856	170.0	1637	170.0	861	170.0	1758	170.0	881	170.0	1918	170.0	881
	60 in	170.0	885	170.0	701	170.0	1063	170.0	797	170.0	1240	170.0	878	170.0	1399	170.0	944	170.0	1552	170.0	996	170.0	1637	170.0	996	170.0	1758	170.0	1008	170.0	1837	170.0	935	170.0	1987	170.0	935
	63 in	170.0	930	170.0	745	170.0	1116	170.0	850	170.0	1240	170.0	940	170.0	1425	170.0	983	170.0	1552	170.0	1008	170.0	1637	170.0	1008	170.0	1758	170.0	1008	170.0	1837	170.0	935	170.0	1987	170.0	935
	66 in	170.0	974	170.0	789	170.0	1189	170.0	903	170.0	1240	170.0	940	170.0	1425	170.0	983	170.0	1552	170.0	1008	170.0	1637	170.0	1008	170.0	1758	170.0	1008	170.0	1837	170.0	935	170.0	1987	170.0	935
	72 in	161.6	1010	169.8	877	134.7	1010	144.6	859	115.4	1010	127.2	842	101.0	1010	114.7	828	89.8	1010	105.6	817	80.8	1010	98.9	807	87.3	1010	90.8	795	57.7	1010	87.8	790	50.5	1010	87.7	789
	76 in	137.4	906	143.6	792	114.5	906	122.0	775	98.1	906	107.1	761	85.9	906	96.2	749	76.3	906	88.2	738	68.7	906	82.3	729	57.3	906	74.7	716	49.1	906	71.2	710	42.9	906	70.6	708
	78 in	127.1	861	132.5	754	105.9	861	112.5	736	90.8	861	98.6	725	79.4	861	88.5	713	70.6	861	81.0	703	63.6	861	75.4	694	53.0	861	68.1	681	45.4	861	64.5	675	39.7	861	63.7	672
	90 in	82.7	646	85.4	574	68.9	646	72.1	584	59.1	646	62.9	554	51.7	646	56.1	545	48.0	646	50.9	537	41.4	646	47.0	530	34.5	646	41.5	519	29.5	646	38.2	511	25.9	646	36.5	507
	96 in	68.2	568	70.1	508	56.8	568	59.1	499	48.7	568	51.4	491	42.6	568	45.8	483	37.9	568	41.4	476	34.1	568	38.1	470	28.4	568	33.4	459	24.3	568	30.5	452	21.3	568	28.7	447
	108 in	47.9	449	48.9	405	39.8	449	41.2	399	34.2	449	35.7	393	28.9	449	31.7	387	26.6	449	28.6	382	23.9	449	26.1	377	20.0	449	22.7	368	17.1	449	20.4	361	15.0	449	18.9	356
	111 in	44.1	425	45.0	385	36.8	425	37.9	379	31.5	425	32.8	373	27.6	425	29.1	367	24.5	425	26.2	362	22.1	425	24.0	358	18.4	425	20.7	350	15.8	425	18.6	343				
	120 in	34.9	364	35.5	331	29.1	364	29.8	326	24.9	364	25.8	321	21.8	364	22.8	317	19.4	364	20.5	313	17.5	364	18.7	309												
	144 in	20.2	253	20.4	233	16.8	253	17.1	230																												

TABLE 16B

Anchor Capacity Table (lbs)																	
Anchor Clip Patterns	Substrate:	2.7k Concrete				3.5k Conc.	Hollow CMU						Filled CMU	PT Wood		Metal	
	Anchor Type:	3/16" Elco Ultracon		1/4" Elco Ultracon		5/16" Elco Ultracon	3/16" Elco Ultracon		1/4" Elco Ultracon		1/4" SS Elco AggreGator	5/16" Elco Ultracon	1/4" SS Elco AggreGator	#10 Steel Screw (G5)	#12 Steel Screw (G5)	#12 Steel Screw (G5)	
	Edge Distance (in):	1"	2-1/2"	1"	2-1/2"	3-1/8"	1"	2-1/2"	1"	2-1/2"	2"	3-1/8"	2"	0.48"	0.54"	0.324"	
	Embedment (in):	1-3/4"	1-3/4"	1-3/4"	1-3/4"	2"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	1-1/4"	2"	1-3/8"	1-3/8"	varies	
2 Anchors @ 5" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 1):		390 lbs	390 lbs	450 lbs	890 lbs	1700 lbs	270 lbs	280 lbs	354 lbs	740 lbs	374 lbs	720 lbs	946 lbs	341 lbs	442 lbs	560 lbs	
4 Anchors @ 3.5" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 2):		780 lbs	780 lbs	790 lbs	1670 lbs	2525 lbs	540 lbs	560 lbs	N/A	1120 lbs	748 lbs	880 lbs	1892 lbs	682 lbs	885 lbs	1120 lbs	
6 Anchors @ 2.71" Min. O.C. / (2) 2x5 Angle Clips / (Fig. 3):		1120 lbs	1120 lbs	958 lbs	2246 lbs	2254 lbs	N/A	840 lbs	N/A	1059 lbs	N/A	1320 lbs	N/A	1022 lbs	1327 lbs	1680 lbs	

FIGURE 1:




FIGURE 2:





FIGURE 3:



ANGLE CLIP (FIGURES 1-3) MUST BE USED IN PAIRS.


TABLE NOTES:

- 1) SEE SHEET 1 FOR INSTRUCTIONS ON USING THE TABLES AND SHEET 25 FOR INFORMATION ON LOADING. SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.
- 2) LINEAR INTERPOLATION BETWEEN MULL LENGTHS AND/OR OPENING WIDTHS IS ALLOWABLE.
- 3) MULLION AND MULLION CLIPS SHOWN ARE NOT TO SCALE. FOR EXACT DIMENSIONS, SEE SHEETS 21-23. HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS SHOWN ON SHEETS 21-23. FIGURES SHOW SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 4) SUBSTRATES: CONCRETE SHALL CONFORM TO ACI 301 SPECIFICATIONS. HOLLOW AND GROUT-FILLED CONCRETE BLOCK UNIT (CMU) SHALL CONFORM TO ASTM C-90. WOOD SHALL BE PRESSURE-TREATED YELLOW SOUTHERN PINE WITH AN SG OF 0.55. ALUMINUM SHALL BE 6063-T5 AND BE A MINIMUM OF .125" THICK. STEEL STUDS TO BE A MINIMUM GRADE 33 AND .045" THICK (18 GAUGE). STRUCTURAL STEEL TO BE AT LEAST .125" THICK AND A36. ALL ANCHORS INTO METAL SHALL EXTEND AT LEAST 3 SCREW THREADS BEYOND THE MATERIAL. #10 & #12 ANCHORS INTO WOOD MAY BE STEEL, 18-8 S.S. OR 410 S.S.

ANCHOR CAPACITY ADJUSTMENT FORMULA:



$$(DP_{REQ}) \times \left(\frac{\text{ANCHOR CAP. FROM TABLE}}{\text{MULLION CAP. FROM TABLE}} \right) = \text{ANCHOR CAP. REQ.}$$

USE THIS FORMULA TO OBTAIN THE "ANCHOR CAPACITY REQUIRED" CORRESPONDING TO AN ACTUAL PRESSURE REQUIREMENT FOR THE OPENING, WHEN IT IS LOWER THAN THE MULLION CAPACITY (FROM THE TABLE) OF THE SELECTED MULLION. IT WILL YIELD A MINIMUM ANCHOR CAPACITY WHICH MAY BE USED TO QUALIFY ADDITIONAL ANCHOR OPTIONS FROM THE ANCHOR CAPACITY TABLE.



PRODUCT REVISED as complying with the Florida Building Code
Acceptance No. 16-0218.03
Expiration Date May 26, 2021

By *Manuel Diaz*
Miami/Dade Product Control



Title: IMPACT-RESISTANT ALUMINUM TUBE MULLIONS
Description: 45 DEGREE BAY MULL SPECS
Series: N/A
Drawing No: 6300JR
Scale: N/A
Date: 08/29/11
Checked By: J. ROSOWSKI
Date: 10/10/14
Rev. By: J. ROSOWSKI
Revision: 10/10/14
NEW MULLS TO SHEETSET

FL CERT. OF AUTH. # 29296

















TABLE B

Mull Dimension (sheet #)	PGT Part #				
	Mullion	Std. Clip	Offset Clip	U-Clip	Angle Clip
1" X 2" X .125" (5)	66605	666113M	6661118M	666243M	666511M
1" X 2" X .375" (6)	666006	666114M	6661119M	666244M	666512M
1" X 2.75" X .375" (7)	66607	666115M	6661120M	666245M	666513M
1" X 2.75" X .650" (8)	66608	666116M	6661121M	666246M	666514M
1" X 3.125" X .500" (9)	66637M	6661116M	6661114M	666242M	666515M
1.25" X 3.188" X .265" (12)	66641M	6661117M	6661113M	666241M	666516M
1.26" X 2.11" X .125" (18)	69370	N/A	N/A	N/A	666517M


NOTES:


- HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS GIVEN ON THIS SHEET.
- SEE SHEETS 5-20 FOR SUGGESTED, APPROXIMATE HOLE LOCATIONS & ANCHOR O.C. DISTANCE.
- SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.

TABLE A

Dimension	Value (in)	For Mullion:
A	1.625	1" X 2" X .125" Aluminum Tube Mullion
B	2.654	
C	0.895	
D	0.740	
A	1.125	1" X 2" X .375" Aluminum Tube Mullion
B	2.404	
C	0.635	
D	0.490	
A	1.875	1" X 2.75" X .375 Aluminum Tube Mullion
B	3.000	
C	0.757	
D	1.118	
E	.450 Min.	1" X 2.75" X .650" Aluminum Tube Mullion
A	1.312	
B	3.000	
C	0.476	
D	0.836	1" X 3.125" X .500" Alum Tube Mull
A	2.000	
B	2.637	
C	0.863	
D	1.137	1.25" X 3.188" X .265" Alum Tube Mull
A	2.625	
B	3.262	
C	0.862	
D	1.762	1.26" X 2.11" X .121" Alum Tube Mull
A	1.813	

PRODUCT REVISED as complying with the Florida Building Code Acceptance No. 16-0218.03 Expiration Date May 26, 2021
By *Manuel Perez*
Miami Dade Product Control






1" X 4" X .125" MULLION 6063-T6 ALUM. X-SECTION

1" X 4" X .375" MULLION 6063-T6 ALUM. X-SECTION


1" X 4" X .375" "T"-MULLION 6063-T6 ALUM. X-SECTION



1.25" X 3.25" X .100" MULLION 6005-T5 ALUM. X-SECTION


1.25" X 3.25" X .624" MULLION 6005-T5 ALUM. X-SECTION

1.25" X 3.94" X .624" MULLION 6005-T5 ALUM. X-SECTION




NOTES:

- HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS GIVEN ON THIS SHEET.
- SEE SHEETS 5-20 FOR SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.




STANDARD CLIP 6063-T6 ALUM. TOPVIEW


CENTER OF ANCHOR HOLE MUST LIE WITHIN THE DASHED BOUNDARY. SEE SHEETS 5-20 FOR THE ANCHOR O.C. DISTANCE. MAXIMUM ANCHOR HOLE DIAMETER: ANCHOR DIAMETER + 1/16".




OFFSET CLIP 6063-T6 ALUM. TOPVIEW



STANDARD CLIP 6063-T6 ALUM. X-SECTION




U-CLIP 6063-T6 ALUM. X-SECTION




2X5 ANGLE CLIP 6063-T6 ALUM. X-SECTION

CENTER OF ANCHOR HOLE MUST LIE WITHIN THE DASHED BOUNDARY. SEE SHEETS 5-20 FOR THE ANCHOR O.C. DISTANCE. MAXIMUM ANCHOR HOLE DIAMETER: ANCHOR DIAMETER + 1/16".



U-CLIP 6063-T6 ALUM. TOPVIEW

CENTER OF ANCHOR HOLE MUST LIE WITHIN THE DASHED BOUNDARY. SEE SHEETS 5-20 FOR THE ANCHOR O.C. DISTANCE. MAXIMUM ANCHOR HOLE DIAMETER: ANCHOR DIAMETER + 1/16".



2X5 ANGLE CLIP 6063-T6 ALUM. TOPVIEW

TABLE C


Dimension	Value (in)	For Mullion:
F	3.687	1" X 4" X .125"
G	1.000	.125"
H	2.680	Aluminum
I	3.000	Tube Mullion
F	3.187	1" X 4" X .375"
G	0.757	.375"
H	2.430	Aluminum
I	3.000	Tube & "T"
F	2.250	1.25" X 3.25"
G	0.750	X .100"
H	1.500	Aluminum
I	3.250	Tube Mullion

TABLE C, CONT.

Dimension	Value (in)	For Mullion:
F	1.938	1.25" X 3.25"
G	0.500	X .624"
H	1.438	Aluminum
I	3.250	Tube Mullion
F	2.625	1.25" X 3.94"
G	1.125	X .624"
H	1.500	Aluminum
I	3.250	Tube Mullion
F	2.813	30° Bay Mull
F	2.875	45° Bay Mull

TABLE D

Mull Dimension (sheet #)	PGT Part #				
	Mullion	Std. Clip	Offset Clip	U-Clip	Angle Clip
1" X 4" X .125" (10)	69364	666111M	6661122M	666241M	666516M
1" X 4" X .375" (11)	66610	666112M	6661123M	666242M	666519M
1" X 4" X .375" "T" (11)	66653	666112M	6661123M	666242M	666519M
1.25" X 3.25" X .100" (13)	20180	6661127M	6661124M	6662410M	6665115M
1.25" X 3.25" X .624" (14)	20181	6661128M	6661125M	6662411M	6665116M
1.25" X 3.94" X .624" (15)	20162	6661117M	6661126M	666241M	666517M
30 Degree (19)	66649	N/A	N/A	N/A	6665110M
45 Degree (20)	66650	N/A	N/A	N/A	6665111M



Title: IMPACT-RESISTANT ALUMINUM TUBE MULLIONS

Description: MULLION AND CLIP DIMENSIONS B

Series: N/A

Scale: N/A

Drawn By: J ROSOWSKI

Checked By: J ROSOWSKI

Date: 08/29/11

Revision: 10/10/14 NEW MULLS TO SHEETSET

PRODUCT REVISED as complying with the Florida Building Code Acceptance No. 16-0218.03 Expiration Date May 26, 2021

By: Manuel Perez Miami Dade Product Control





TABLE E


Mull Dimension (sheet #)	PGT Part #			
	Mullion	Std. Clip	U-Clip	Angle Clip
2" X 4" X .25" (16)	66602	666261M	666271M	6665112M
2" X 6" X .25" (17)	66604	666262M	666272M	6665113M

NOTES:







- 1) HOLES TO BE DRILLED IN THE FIELD FOLLOWING DIMENSIONAL RESTRICTIONS GIVEN ON THIS SHEET.
- 2) SEE SHEETS 5-20 FOR SUGGESTED, APPROXIMATE HOLE LOCATIONS.
- 3) SEE SHEETS 2-4 FOR GENERAL INSTALLATION METHODS.



2" X 4" X .25"
MULLION
6063-T6 ALUM.
X-SECTION



2" X 6" X .25"
MULLION
6063-T6 ALUM.
X-SECTION




PGT
1070 TECHNOLOGY DRIVE
N. VENICE, FL 34275
P.O. BOX 1529
NOKOMIS, FL 34274
FL CERT. OF AUTH.# 29296

IMPACT-RESISTANT ALUMINUM TUBE MULLIONS
Description: **MULLION AND CLIP DIMENSIONS C**
Series: **N/A**
Drawing No.: **6300JR**
Scale: **N/A**
Sheet: **23 of 25**
Rev: **B**
Date: **08/29/11**
Checked By: **J ROSOWSKI**
Date: **10/10/14**
Revised: **J ROSOWSKI**
Revision: **NEW MULLS TO SHEETSET**

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. **16-0218.03**
Expiration Date **May 26, 2021**
By **Manuel Suarez**
Miami Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
A-E 4/8/16
STATE OF
FLORIDA
PROFESSIONAL ENGINEER
A. LYNN MILLER, P.E.
FL P.E.# 58705

EXAMPLE 1: SINGLE VERTICAL MULLION



THE BUILDING SUBSTRATE IS KNOWN TO BE WOOD ON ALL FOUR SIDES. THE WINDOW FRAME DEPTH IS 2-1/4". THE OPENING REQUIRES A DESIGN PRESSURE OF +60.0/-60.0 PSF.

1) INITIALLY ASSUMING THAT A 1" WIDE MULLION IS SUITABLE, THE MULLION LENGTH IS 72" AND THE OPENING WIDTH IS 32"+32"+1"=65". REFERENCING SHEET 25, THE COLUMN USING RECTANGULAR LOADING MUST BE USED. SCAN THE MULLION TABLES FOR A MULLION THAT IS AT LEAST THE WINDOW FRAME DEPTH OF 2-1/4" AND WILL MEET OR EXCEED THE REQUIRED DESIGN PRESSURE OF +60.0/-60.0 PSF. IF THE TABLE DOES NOT SHOW THE EXACT SIZE, USE THE NEXT LARGER SIZE AVAILABLE.

FROM TABLE 3A, SHEET 7, THE 1" X 2.75" X .375" MULLION (LENGTH = 72", OPENING WIDTH = 70") MEETS THE DEPTH REQUIRED, HOWEVER THE DESIGN PRESSURE IS +/-58.3 PSF AND WOULD NOT BE SUITABLE FOR THIS APPLICATION.

FROM TABLE 4A, SHEET 8, THE 1" X 2.75" X .650" MULLION (LENGTH = 72", OPENING WIDTH = 70") HAS A DESIGN PRESSURE OF +/-72.7 PSF WHICH EXCEEDS THE REQUIREMENTS FOR THE OPENING AND MAY BE USED IN THIS APPLICATION. NOTE THE ANCHOR CAPACITY REQUIRED OF 636 LBS.

2) USE TABLE 4B TO FIND THE ANCHOR TYPE, ANCHOR QUANTITY AND CLIP TYPE REQUIRED FOR THE WOOD SUBSTRATE. BOTH THE STANDARD CLIP WITH (4) #12 ANCHORS AND THE 2X5 ANGLE CLIPS WITH (4) #12 ANCHORS HAVE A CAPACITY OF 885 LBS. THOUGH EITHER ONE COULD BE USED, THE STANDARD CLIP IS EASIER TO INSTALL.

3) VERIFY THE DESIGN PRESSURE OF THE FENESTRATION PRODUCTS USED WITH THIS MULLION SYSTEM. THE LOWER DESIGN PRESSURE, OF MULLIONS OR FENESTRATION PRODUCTS, WILL APPLY TO THE OVERALL ASSEMBLY. FINAL DESIGN PRESSURE REQUIRES THAT THE BOTH THE MULLION AND THE FENESTRATION PRODUCT BE INSTALLED IN ACCORDANCE WITH THE INSTALLATION SPECIFICATIONS INTO RESPECTIVE SUBSTRATES AND FENESTRATION PRODUCTS TO MULLION.

IN THIS EXAMPLE, THE DESIGN PRESSURE REQUIRED WAS +/-60.0 PSF. THE OVERALL MULLION SYSTEM WAS DETERMINED TO BE 72.7 PSF WITH AN ANCHOR CAPACITY OF 636 LBS. ALTERNATIVELY, THE ANCHOR CAPACITY ADJUSTMENT FORMULA COULD HAVE BEEN USED TO CALCULATE THE ANCHOR CAPACITY REQUIRED FOR THE EXACT DESIGN PRESSURE OF 60 PSF:

$$(60 \text{ PSF}) \times \left(\frac{636 \text{ LBS}}{72.7 \text{ PSF}} \right) = 524.9 \text{ LBS} \quad (\text{MAY BE USED TO QUALIFY \# 10 STEEL SCREWS FROM TABLE 4B})$$

THE BUILDING SUBSTRATE IS KNOWN TO BE CMU ON THE JAMBS AND USES A CONCRETE HEADER AND SILL. THE WINDOW FRAME DEPTH IS 2-3/8". THE OPENING REQUIRES A DESIGN PRESSURE OF +50.0/-55.0 PSF.

FOR THE VERTICAL MULLION:

1) INITIALLY ASSUMING THAT A 1" WIDE MULLION IS SUITABLE, THE MULLION LENGTH IS 32"+72"+1"=105" AND THE OPENING WIDTH IS 36"+36"+1"=73". REFERENCING SHEET 25, THE COLUMN USING RECTANGULAR LOADING SHALL BE USED. SCAN THE MULLION TABLES FOR A MULLION THAT IS AT LEAST THE WINDOW FRAME DEPTH OF 2-3/8" AND WILL MEET OR EXCEED THE REQUIRED DESIGN PRESSURE OF +50.0/-55.0 PSF. IF THE TABLE DOES NOT SHOW THE EXACT SIZE, USE THE NEXT LARGER SIZE AVAILABLE.

FROM TABLE 3A, SHEET 7, THE 1" X 2.75" X .375" MULLION (LENGTH = 108", OPENING WIDTH = 80") MEETS THE DEPTH REQUIRED, HOWEVER THE DESIGN PRESSURE IS +/-15.1 PSF AND WOULD NOT BE SUITABLE FOR THIS APPLICATION.

FROM TABLE 12A, SHEET 16, THE 2" X 4" X .250" MULLION (LENGTH = 108", OPENING WIDTH = 80") HAS A DESIGN PRESSURE OF +/-64.7 PSF WHICH EXCEEDS THE REQUIREMENTS FOR THE OPENING AND MAY BE USED IN THIS APPLICATION. NOTE THE ANCHOR CAPACITY REQUIRED OF 971 LBS.

BECAUSE IT IS NOW KNOWN THAT THE MULLION WILL ADD 2" TO THE WIDTH OF THE MULLED UNIT, THE ADJUSTED OPENING WIDTH IS 36"+36"+2"=74", NOT 73" AS PREVIOUSLY ASSUMED. VERIFY THAT THE DESIGN PRESSURE IS STILL APPLICABLE FOR THE ADJUSTED OPENING. ALTERNATIVELY, THE WINDOW WIDTHS MAY BE REDUCED TO MAINTAIN THE 73" DIMENSION (35-1/2"+35-1/2"+2"=73").

2) USE TABLE 12B TO FIND THE ANCHOR TYPE, ANCHOR QUANTITY AND CLIP TYPE REQUIRED FOR THE CONCRETE SUBSTRATE. IN THIS EXAMPLE, ASSUME THE POURED CONCRETE HEADER AND SILL ARE 8" WIDE. IF THE MULLION CLIP WERE TO BE CENTERED WITHIN THE 8", CARE MUST BE TAKEN TO MAINTAIN THE FASTENER'S EDGE DISTANCE. USING THE STANDARD CLIP WITH (6) 3/16" ULTRACON ANCHORS AT AN EDGE DISTANCE OF 2-1/2" GIVES AN ANCHOR CAPACITY OF 1050 LBS WHICH IS GREATER, AND THEREFORE SUITABLE, FOR THE REQUIRED ANCHOR CAPACITY OF 971 LBS.

FOR THE HORIZONTAL MULLIONS:

BECAUSE THE VERTICAL MULL WILL BE A 2" X 4" X .250" MULLION, IN THIS EXAMPLE WE WILL MATCH THE HORIZONTAL AND VERTICAL MULLIONS, ALTERNATIVELY, ANOTHER MULLION TYPE COULD BE CHOSEN.

1) THE MULLION LENGTH IS 36" AND THE OPENING HEIGHT IS 32"+72"+2"=106". REFERENCING SHEET 25, THE COLUMN USING TRAPEZOIDAL/TRIANGULAR LOADING MAY BE USED. FROM TABLE 12A, SHEET 16, THE 2" X 4" X .250" MULLION (@ LENGTH = 42", OPENING HEIGHT = 120") HAS A DESIGN PRESSURE OF +/-170.0 PSF WHICH EXCEEDS THE REQUIREMENTS FOR THE OPENING AND MAY BE USED IN THIS APPLICATION. NOTE THE ANCHOR CAPACITY REQUIRED OF 521 LBS.

2) USE TABLE 12B TO FIND THE ANCHOR TYPE, ANCHOR QUANTITY AND CLIP TYPE REQUIRED FOR THE CMU SUBSTRATE. IN THIS EXAMPLE, ASSUME THE CMU JAMBS ARE 8" WIDE. IF THE MULLION CLIP WERE TO BE CENTERED WITHIN THE 8", CARE MUST BE TAKEN TO MAINTAIN THE FASTENER'S EDGE DISTANCE. USING THE 2X5 ANGLE CLIPS WITH (4) 3/16" ULTRACON ANCHORS AT AN EDGE DISTANCE OF 1" GIVES AN ANCHOR CAPACITY OF 540 LBS WHICH IS GREATER, AND THEREFORE SUITABLE, FOR THE REQUIRED ANCHOR CAPACITY OF 521 LBS.

4) FOR THE U-CLIP IN THE HORIZONTAL MULLION TO VERTICAL MULLION, USE THE SAME ANCHOR CAPACITY OF 521 LBS. TABLE 12B FOR THE U-CLIP SHOWS THE ANCHOR CAPACITY IS 1074 LBS WHEN USING 3 ANCHORS, WHICH IS GREATER, AND THEREFORE SUITABLE, FOR THE REQUIRED ANCHOR CAPACITY REQUIREMENT OF 521 LBS. THE ANCHOR TYPE IS A #12 STEEL SCREW.

FROM THE ABOVE STEPS, OUR MULLION DESIGN PRESSURE IS:

+/-64.7 PSF FROM THE VERTICAL MULLION;


+/-170.0 PSF FROM THE 36" HORIZONTAL MULLION ATTACHING TO CMU;

+/-170.0 PSF FROM THE 36" HORIZONTAL MULLION ATTACHING TO THE VERTICAL MULLION (INTERSECTION).

THE LOWEST DESIGN PRESSURE IS +/-64.7 PSF AND WOULD APPLY TO ALL OF THE MULLIONS.

VERIFY THE DESIGN PRESSURE OF THE FENESTRATION PRODUCTS USED WITH THIS MULLION SYSTEM. THE LOWER DESIGN PRESSURE, OF MULLIONS OR FENESTRATION PRODUCTS, WILL APPLY TO THE OVERALL ASSEMBLY. FINAL DESIGN PRESSURE REQUIRES THAT THE BOTH THE MULLION AND THE FENESTRATION PRODUCT BE INSTALLED IN ACCORDANCE WITH THE INSTALLATION SPECIFICATIONS INTO RESPECTIVE SUBSTRATES AND FENESTRATION PRODUCTS TO MULLION.


EXAMPLE 2: MULTIPLE MULLIONS




		1070 TECHNOLOGY DRIVE N. VENICE, FL 34275 P.O. BOX 1529 NOKOMIS, FL 34274 FL CERT. OF AUTH. # 29296	
IMPACT-RESISTANT ALUMINUM TUBE MULLIONS		EXAMPLES	
Title:	Description:	Drawing No:	Sheet:
Series:	Scale:	Checked By:	24 of 25
Drawn By:	Date:	Date:	Rev:
J. ROSOWSKI	08/29/11	10/10/14	B
Rev. By:	Revision:	NEW MULLS TO SHEETSET	
J. ROSOWSKI	10/10/14		

PRODUCT REVISED
 as complying with the Florida
 Building Code
 Acceptance No. 16-0218-03
 Expiration Date May 26, 2021


By *Manuel Perez*
 Miami Dade Product Control




EXAMPLES OF RECTANGULAR LOADING:




LOADING OF VERTICAL MULLION
SILL OF WINDOWS NOT ANCHORED




LOADING OF VERTICAL MULLION
WITH INTERSECTING HORIZONTAL MULLIONS




LOADING OF VERTICAL MULLION
SILL OF WINDOWS NOT ANCHORED



LOADING OF HORIZONTAL MULLION
WITH INTERSECTING VERTICAL MULLION




LOADING OF VERTICAL MULLION
PANEL OF HINGED DOOR IS NOT CAPTURED OR ANCHORED




LOADING OF VERTICAL MULLION
WITH INTERSECTING HORIZONTAL MULLIONS


EXAMPLES OF TRAPEZOIDAL/TRIANGULAR LOADING:




LOADING OF HORIZONTAL MULLION




LOADING OF HORIZONTAL MULLION




LOADING OF VERTICAL MULLION




LOADING OF (2) HORIZONTAL MULLIONS




LOADING OF HORIZONTAL MULLION



LOADING OF HORIZONTAL
MULLION



LOADING OF VERTICAL
MULLION



LOADING OF HORIZONTAL
MULLION

NOTES:

1) DRAWINGS ARE
RERPRESENTATIONS OF TYPICAL
CONFIGURATIONS.
CONFIGURATIONS NOT SHOWN
MAY BE EXTRAPOLATED FROM
THOSE SHOWN.

2) IF THE LOADING TYPE CANNOT
BE DETERMINED, USE
RECTANGULAR LOADING.

3) SEE PRODUCTS' APPROVAL FOR
ACTUAL ANCHOR LOCATIONS.

Title: IMPACT-RESISTANT ALUMINUM TUBE MULLIONS

LOADING EXAMPLES			
Series:	N/A	Scale:	N/A
Drawn By:	J ROSOWSKI	Checked By:	6300JR
Rev. By:	J ROSOWSKI	Date:	08/29/11
Revision:	10/10/14	Rev:	B

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No 16-0218.03
Expiration Date 12/26/2021
By *Manuel Pires*
Miami/Dade Product Control

ANTHONY LYNN MILLER
LICENSE
No. 58705
A. LYNN MILLER, P.E.
FL P.E.# 58705